

STATE OF
COLORADO

Housey - DNR, Melissa <melissa.housey@state.co.us>

Comments and Conditions of Approval

Housey - DNR, Melissa <melissa.housey@state.co.us>

Mon, May 5, 2014 at 5:03 PM

To: "Carlile, Justin" <Justin.Carlile@conocophillips.com>

Hi Justin

The COGCC has received and reviewed the Letter Correspondence dated April 21, 2014 regarding Conoco Phillips response to the public comments on Prosper Farms 4-65 13-14 1H.

Based on our review, please address the following comments.

Comments

- 1) Fourth sentence of the fourth paragraph: Conoco Philips has stated that the proposed road base material "does not generate a lot of dust." Please quantify this statement or remove the statement from the BMPs.
- 2) Sixth sentence of the fourth paragraph: Conoco Philips states that "once the road is put into service, Conoco Philips will take additional measures to reduce dust..." Please advise COGCC as to what additional measures will be taken.

In addition to the above stated comments, the following COAs will be applied to the Form 2A permit.

Conditions of Approval

- 1) Operator will mitigate dust by applying water prior to potentially dust generating activities and visual emissions of dust (i.e. formation of dust clouds).
- 2) During mobilization, construction, drilling, and fluids transfer operations, Operator will enforce reduced speeds of, no greater than 15 miles per hour from within 500 feet of either direction of the Hurd property along the access route. Speed reduction warning signs will be posted along N. Hayesmount road, 1,000 and 500 feet north of the entrance to the access road and speed limit signs will be posted along the access road as allowed by County regulations [The operator will strictly enforce the speed limits along the access road]. The use of Jake Brakes is prohibited.
- 3) Operator will design the site layout in such a manner that will minimize noise impacts to the resident to the north.

4) Operator will submit a Form 42 Notice of Notification, Notice of Intent to Construct 48 hours prior to commencement of construction activities.

Thank You

Melissa

Melissa M. Housey, P.G.

Oil and Gas Location Assessment Specialist

Southeast



P 303.894.2100 x5194 | F 303.894.2109

1120 Lincoln Street, Suite 801, Denver, CO 80203

melissa.housey@state.co.us | www.colorado.gov/cogcc