

DRILLING PROGNOSIS

KGH 3-3H Meagher
Section 3, T1S-R104W
Rio Blanco County, Colorado

Surface Location: 3802' FSL, 419 FEL, Section 3, T1S-R1-4W

Bottom Hole Location: 1750' FNL, 1320 FEL, Section 2, T1S-R104W
(5280' lateral @ azimuth = 60)

Ground Elevation: 6111.3' MSL
Estimated KB Elevation: 6131' MSL

<u>Formation</u>	<u>TVD</u>	<u>Subsea</u>
Lower Sego	4148	+1952
Buck Tongue	4314	+1786
Castlegate	4513	+1587
Mancos A	5466	+634
Mancos B	5656	+444
Pay Zone	5751	+349