

FORM
6Rev
12/05State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400612136

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 95960

Contact Name: Chris Beilby

Name of Operator: WEXPRO COMPANY

Phone: (307) 352-7566

Address: P O BOX 45003

Fax: (307) 352-7575

City: SALT LAKE CITY State: UT Zip: 84145-

Email: chris.beilby@questar.com

For "Intent" 24 hour notice required,

Name: Waldron, Emily

Tel: (970) 819-9609

COGCC contact:

Email: emily.waldron@state.co.us

API Number 05-081-06165-00

Well Name: JACKS DRAW UNIT

Well Number: 13

Location: QtrQtr: NWSW Section: 22 Township: 12N Range: 97W Meridian: 6

County: MOFFAT

Federal, Indian or State Lease Number: 38665

Field Name: POWDER WASH

Field Number: 69800

☒ Notice of Intent to Abandon☐ Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.984865

Longitude: -108.285927

GPS Data:

Date of Measurement: 06/28/2010

PDOP Reading: 2.3

GPS Instrument Operator's Name: Larry D. Brown

Reason for Abandonment:

☐ Dry☒ Production for Sub-economic☐ Mechanical Problems☐ Other

Casing to be pulled:

☐ Yes☒ No

Estimated Depth: 5814

Fish in Hole:

☐ Yes☒ No

If yes, explain details below

Wellbore has Uncemented Casing leaks:

☐ Yes☒ No

If yes, explain details below

Details:

Current and Previously Abandoned Zones

| Formation | Perf. Top | Perf. Btm | Abandoned Date | Method of Isolation | Plug Depth |
|------------|-----------|-----------|----------------|---------------------|------------|
| FORT UNION | 5108 | 5986 | | RETAINER/SQUEEZED | 5058 |

Total: 1 zone(s)

Casing History

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bot | Cement Top | Status |
|-------------|--------------|----------------|-----------------|---------------|--------------|------------|------------|--------|
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 6,166 | 900 | 6,166 | 3,550 | CALC |

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth _____ with _____ sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 15 sks cmt from 3480 ft. to 3620 ft. Plug Type: CASING Plug Tagged: ☐
Set 15 sks cmt from 0 ft. to 230 ft. Plug Type: CASING Plug Tagged: ☐
Set 15 sks cmt from 0 ft. to 50 ft. Plug Type: ANNULUS Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 5108 ft. with 50 sacks. Leave at least 100 ft. in casing 5058 CICR Depth

Perforate and squeeze at 375 ft. with 45 sacks. Leave at least 100 ft. in casing 230 CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged: ☐

Set 65 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☒ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. of _____ inch casing Plugging Date: _____

*Wireline Contractor: _____ *Cementing Contractor: _____

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1103 ☐ Yes ☐ No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Chris Beilby

Title: Completion Manager Date: _____ Email: chris.beilby@questar.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

Expiration Date: _____

COA Type

Description

| | |
|--|--|
| | |
|--|--|

Attachment Check List

Att Doc Num

Name

| | |
|-----------|-----------------------------|
| 400612148 | PROPOSED PLUGGING PROCEDURE |
| 400612149 | WELLBORE DIAGRAM |
| 400612150 | OTHER |

Total Attach: 3 Files

General Comments

User Group

Comment

Comment Date

| | | |
|--|--|--|
| | | |
|--|--|--|

Total: 0 comment(s)