

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 16 South, Range 53 West, Section 18: All

Total Acres in Described Lease: 630 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 685 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 962 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 1552 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

This APD is for a sidetrack well. Nearest wellbore permitted or completed in the same formation is the Long View Farm 33-19-16-53, API 05-073-06509.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
------------------------	----------------	-------------------------	-------------------------------	--------------------------------------

CHEROKEE	CHRK			
----------	------	--	--	--

DRILLING PROGRAM

Proposed Total Measured Depth: 9831 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 1552 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? Yes

Will oil based drilling fluids be used? Yes

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Other

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Fluids will be injected in disposal offsite. Solids will be treated onsite. Salt or oil-based muds will be used in production hole section of well. Pit liner land fill. See attachments for proposed mud treatment program for both water & oil-based cuttings

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	94	0	40			
SURF	17+1/2	13+3/8	54.5	0	3010	1750	3010	0
1ST	12+1/4	9+5/8	36	0	5897	751	5897	0
2ND	7+7/8	5+1/2	17	5597	9831	504	9831	5597

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments This APD is for one horizontal sidetrack to the Cherokee formation. Doc 400596320 is APD for the vertical pilot well. Doc 400610529 is APD for the second horizontal sidetrack to the Atoka formation.

Attached as "other" are 4 documents describing Pioneer's proposed mud treatment program for both water and oil-based cuttings as they apply to the sidetrack wellbores, to address questions under the Drilling & Waste tab.

A pit will be used for drilling and completion and will be 100'x100', with a 10' depth + freeboard. Form 15 Pit Permit will be submitted.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ann Stephens _____

Title: Regulatory Manager _____ Date: _____ Email: regulatory@petro-fs.com _____

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC _____ Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

<u>COA Type</u>	<u>Description</u>

Best Management Practices

No BMP/COA Type

Description

<u>No BMP/COA Type</u>	<u>Description</u>
1 Planning	Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds and implement dust control, as needed. Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by operator, its employees, or contactors can cross through fences on the leased premises.

2	Construction	Waste Management and Disposal: A skid-mounted cage/dumpster is placed at a well pad during construction and is utilized while crews are onsite during drilling and completion activities. Upon completion of these activities the dumpster is removed from the site.
3	General Housekeeping	Good housekeeping practices will be used to reduce the risk of spills or other accidental exposure of materials and substances to Stormwater runoff. The following housekeeping practices will be followed onsite during the construction project: <ul style="list-style-type: none"> • No solid materials, including building materials, shall be discharged to State waters. • Vehicular traffic will be minimized as much as possible to reduce nuisance dust and prevent further soil erosion. • Any trash generated during the project will be disposed of properly. • Any chemicals used will be kept to a minimum. Any chemical or oil spills will be cleaned up immediately in accordance with established company procedures. • Store all materials in a neat and orderly manner in their appropriate containers. • Follow manufacturers' recommendations and company policies for proper use and disposal of products. • Monitor on-site vehicles for leaks.
4	Storm Water/Erosion Control	Structural Practices for Erosion and Sediment Control: Structural BMPs include, but are not limited to: diversion ditch, earthen berm, silt fence, straw bale, wattle (straw/mulch/bark), rip rap, bonded fiber matrix, erosion control blanket, coconut matting, slash, brush dam, sediment retention ponds, and turnout.
5	Storm Water/Erosion Control	Non-Structural Practices for Erosion and Sediment Control: Nonstructural BMPs include, but are not limited to: preservation of existing vegetation, vegetative buffer zones, slope roughening, and protection of trees.
6	Material Handling and Spill Prevention	Materials Handling and Spill Prevention: All drums and totes temporarily stored onsite shall be inspected regularly to ensure integrity. Secondary containment shall be utilized when necessary or required by SPCC regulations. Spill response equipment shall be available in the event of a spill or release. Onsite personnel are instructed to report all spills; Operator shall investigate all spills to ensure proper cleanup/remediation measures and required reporting protocol is implemented. Spill cleanup materials are onsite in the event of a release. All spills are reported according to the state and federal requirements.
7	Pre-Construction	Remove only the minimum amount of vegetation necessary for the construction of roads and facilities. Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation. No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.
8	Drilling/Completion Operations	The drilling pit will be lined.
9	Interim Reclamation	Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.
10	Final Reclamation	All surface restoration shall be accomplished to the satisfaction of Owner. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner. Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC)

Total: 10 comment(s)

Attachment Check List

Att Doc Num	Name
400610531	WELL LOCATION PLAT
400610594	OTHER
400610595	OTHER
400610596	OTHER
400610597	OTHER
400610598	WELLBORE DIAGRAM
400614338	DIRECTIONAL DATA
400614357	DEVIATED DRILLING PLAN

Total Attach: 8 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)