

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400568985

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 8960 4. Contact Name: Brandon Dykes
 2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-6111
 3. Address: 410 17TH STREET SUITE #1400 Fax: (720) 279-2331
 City: DENVER State: CO Zip: 80202

5. API Number 05-123-38707-01 6. County: WELD
 7. Well Name: Antelope Well Number: T44-P41-18HC
 8. Location: QtrQtr: SWSE Section: 18 Township: 5N Range: 62W Meridian: 6
 Footage at surface: Distance: 610 feet Direction: FSL Distance: 1396 feet Direction: FEL
 As Drilled Latitude: 40.393790 As Drilled Longitude: -104.361560

GPS Data:
 Date of Measurement: 04/24/2014 PDOP Reading: 2.5 GPS Instrument Operator's Name: Brian Rottinghaus

** If directional footage at Top of Prod. Zone Dist.: 697 feet. Direction: FSL Dist.: 956 feet. Direction: FEL
 Sec: 18 Twp: 5N Rng: 62W
 ** If directional footage at Bottom Hole Dist.: 470 feet. Direction: FNL Dist.: 992 feet. Direction: FEL
 Sec: 18 Twp: 5N Rng: 62W

9. Field Name: WATTENBERG 10. Field Number: 90750
 11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 02/20/2014 13. Date TD: 03/07/2014 14. Date Casing Set or D&A: 03/07/2014

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 11158 TVD** 6503 17 Plug Back Total Depth MD 11158 TVD** 6503

18. Elevations GR 4634 KB 4651 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
MUD,CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0		392	0	471	CALC
1ST	8+3/4	7	26	0	6,966	738	0	6,966	CBL
1ST LINER	6+1/8	4+1/2	11.6	6722	11,158				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
	OPEN HOLE	7,600	175	6,966	7,700

Details of work:

Ran drill string open ended to 7600'. pumped 175 sx. cmt. pulled out circulated string clean.

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,227		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,372		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

OH logs were not run on this well because offset logs were run on the Antelope 34-18 (API# 05-123-30517-00); which is within 800' of this pad.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Brandon Dykes

Title: Drilling Engineering Tech

Date: _____

Email: bdykes@bonanzacr.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400615499	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400615522	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400615457	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400615459	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400615460	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400615664	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)