

FORM

2

Rev  
08/13

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400537164

## APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

02/10/2014

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_Refilling ☒ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Mead

Well Number: RWF 43-23

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER

State: CO

Zip: 80202

Contact Name: Reed Haddock

Phone: (303)606-4086

Fax: (303)629-8268

Email: reed.haddock@wpxenergy.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030107

## WELL LOCATION INFORMATION

QtrQtr: NESE Sec: 23 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.510015

Longitude: -107.846945

Footage at Surface: 2293 feet FNL/FSL FSL 211 feet FEL/FWL FEL

Field Name: RULISON

Field Number: 75400

Ground Elevation: 5604

County: GARFIELD

GPS Data:

Date of Measurement: 01/13/2010 PDOP Reading: 2.2 Instrument Operator's Name: J. Kirkpatrick

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FSL 2250 FSL 203 FEL 2250 FSL 203 FEL  
 Sec: 23 Twp: 6S Rng: 94W Sec: 23 Twp: 6S Rng: 94W

## LOCATION SURFACE &amp; MINERALS &amp; RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply)

☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lease previously submitted.

Total Acres in Described Lease: 240 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 211 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 711 Feet  
Building Unit: 699 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 1709 Feet  
Above Ground Utility: 817 Feet  
Railroad: 2038 Feet  
Property Line: 211 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 12/13/2013

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 399 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 203 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

320 Acre CA COC60381

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-66	320	E/2

## DRILLING PROGRAM

Proposed Total Measured Depth: 8310 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 399 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drlg fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48#	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	0	1100	383	1100	0
1ST	7+7/8	4+1/2	11.6#	0	8310	648	8310	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☒ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments Pad has not been built and will have modifications shown on the amended Form 2A.  
Cement 200' above uppermost MVRD sand. CA COC60381.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 419862

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Reed Haddock

Title: Regulatory Specialist Sta Date: 2/10/2014 Email: reed.haddock@wpenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

### API NUMBER

05 045 20050 00

### **Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<b><u>COA Type</u></b>	<b><u>Description</u></b>
Drilling/Completion Operations	Updated Drilling Waste Management information and added COA based on review of Form 2A doc #400538841.
Drilling/Completion Operations	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
Drilling/Completion Operations	<p>1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE.</p> <p>2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.</p> <p>3) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFICATION BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE MAMM CREEK FIELD NOTICE TO OPERATORS.</p> <p>4) THE PROPOSED SURFACE CASING SHOULD BE MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST DEDICATED* WATER WELL WITHIN 1-MILE IS 320 FEET DEEP.</p>
Drilling/Completion Operations	In the event that the onsite cuttings trench and cut backfill area cannot handle all of the drill cuttings generated during drilling, the operator shall submit a form 4 Sundry for prior approval to send the excess cuttings to an alternate Form 2A permitted cutting trench pad.

### **Best Management Practices**

<b><u>No</u></b>	<b><u>BMP/COA Type</u></b>	<b><u>Description</u></b>

### **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.
---

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
400537164	FORM 2 SUBMITTED
400551771	LOCATION DRAWING
400551774	WELL LOCATION PLAT

Total Attach: 3 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	A recent email from the operator states possilbe BHL and SHL possible of some or all of these refiles, will have to receive the changes to determine the need to re-submit the changes for these pending refiles or the need to refile all of these.	5/5/2014 11:29:07 AM
Permit	Final review completed on this refile. No LGD comments.	4/24/2014 1:44:06 PM
Permit	Operator supplied the refile statements.	4/24/2014 1:43:33 PM
LGD	pass, gdb	2/26/2014 2:18:36 PM
LGD	pass, gdb	2/26/2014 2:18:36 PM
Permit	Passed completeness.	2/12/2014 8:26:27 AM

Total: 6 comment(s)