

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400548009

Date Received:

02/12/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: BAT

Well Number: 34C-24-07-96

Name of Operator: URSA OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1050 17TH STREET #2400

City: DENVER State: CO Zip: 80265

Contact Name: Shauna DeMattee

Phone: (720)508-8350

Fax: ()

Email: sdemattee@ursaresources.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: NESW Sec: 24 Twp: 7S Rng: 96W Meridian: 6

Latitude: 39.420644

Longitude: -108.060116

Footage at Surface: 1830 feet FNL/FSL FSL 2031 feet FEL/FWL FWL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 5183

County: GARFIELD

GPS Data:

Date of Measurement: 08/05/2010 PDOP Reading: 2.4 Instrument Operator's Name: Scott E. Aibner

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

743 FSL 1954 FEL 743 FSL 1954 FEL
Sec: 24 Twp: 7S Rng: 96W Sec: 24 Twp: 7S Rng: 96W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____

Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

The S2S2 of Sec. 24, T7S, R96W and the N2 of Sec. 25, T7S, R96W. (See Comments)

Total Acres in Described Lease: 480 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC027825

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 590 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 262 Feet
Building Unit: 1377 Feet
High Occupancy Building Unit: 4407 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 218 Feet
Above Ground Utility: 355 Feet
Railroad: 4344 Feet
Property Line: 733 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 305 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 743 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

The WFCM is the target formation for this well.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-116	588	L1,5,6,NENE,S2NE,S2

DRILLING PROGRAM

Proposed Total Measured Depth: 6300 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 305 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 608

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

If cuttings meet Table 910 they will be beneficially reused.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	84#	0	60	111	60	0
SURF	12+1/4	8+5/8	32#	0	1874	463	1874	0
1ST	7+7/8	4+1/2	11.6#	0	6300	548	6300	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments The BMPs for this well were approved with the Speakman A Pad (Location ID # 422301). The pad has been built, and there will not be additional surface disturbance at the pad location. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not within a wildlife Restricted Surface Occupancy Area. I certify that there have been no changes on land use, lease description. This well is producing from Federal Lease COC027825 which is part of the 588 acre unit created by Spacing Order 139-116. The minerals in this spacing unit are Federal and fee. First String / Production will be > 500 feet above TOG. Please see attached plat for reference to cultural setbacks. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the proposed BAT 34B-24-07-96.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 422301

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Shauna DeMattee

Title: Permit Representative Date: 2/12/2014 Email: sdematttee@ursaresources.co

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/30/2014

Expiration Date: 05/29/2016

API NUMBER

05 045 22424 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE. (2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE. (3) CEMENT ON PRODUCTION CASING (4-1/2" FIRST STRING) MUST EXTEND INTO THE SURFACE CASING (MINIMUM 200' LAP ABOVE SURFACE CASING SHOE) TO PROVIDE ISOLATION OF THE MESAVERDE GROUP AND ANY PORTION OF THE WASATCH FORMATION THAT IS NOT OTHERWISE COVERED BY SURFACE CASING. VERIFY PRODUCTION CASING CEMENT WITH A CBL.

Best Management Practices

No BMP/COA Type

Description

--	--	--

Applicable Policies and Notices to Operators

Piceance Rulison Field - Notice to Operators.
NW Colorado Notification Policy.
Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num

Name

400548009	FORM 2 SUBMITTED
400548011	WELL LOCATION PLAT
400548013	DEVIATED DRILLING PLAN
400551510	DIRECTIONAL DATA

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed. No LGD comments.	5/29/2014 2:08:39 PM
LGD	pass, gdb	3/3/2014 4:28:21 PM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.	2/27/2014 9:00:51 AM
Permit	Passed completeness.	2/14/2014 11:14:47 AM

Total: 4 comment(s)