

WELLBORE DIAGRAM

Peterson Energy Operating

392 Ventures 22CD

SENW Sec. 22, T6N-R67W

SHL: 1543' FNL, 2405' FWL

BHL: 1287' FNL, 1370' FEL

Weld County, CO

05-123-34000

Updated

5/5/2014

SMS

PROPOSED

G.L.= 4783

K.B.= 4799

16

8-5/8" set at 457'

Cmt't w/ 217 sx to Surf.

CBL TOC: 1060'

<<

>>

Niobrara B perf f/ 7234-7240 ft, 6 spf

Frac Niobrara C & B w/ 271,000 gals slickwater & 240,000 lbs 30/50 white sand

<<

>>

Niobrara C perf f/ 7304-7310 ft, 6 spf

<<

>>

Codell: 7416-7425 ft, 4 spf

Frac 2/29/12: 221,256 gal slickwater containing 148,985# 30/50 sand

Niobrara: 7096'

Codell: 7412'

PDTD= 7542'

TD MD= 7585'

TD VD=7337'

4-1/2" 11.6# CSG @ 7561' (7-7/8" O.H.)

Cmt'd w/ 697 sx