

WELLBORE DIAGRAM

Peterson Energy Operating 392 Ventures 22AD

SENW Sec. 22, T6N-R67W

SHL: 1520' FNL, 2294' FWL

BHL: 1349' FNL, 1274' FWL

Weld County, CO

05-123-34002

Updated

3/3/2012

RO

G.L.= 4784

K.B.= 4800

16

8-5/8" set at 461'

Cmt't w/ 265 sx to Surf.

CBL TOC: 1756'

Niobrara: 6967'

Codell: 7287'

Codell: 7290'-7302', 4 spf

Frac 3/3/12: 199,411 gal slickwater containing 121,538# 30/50 sand - Screen-out.

PDTD= 7490'

TD MD= 7495'

TD VD=7372'

4-1/2" 11.6# CSG @ 7495' (7-7/8" O.H.)

Cmt'd w/ 729 sx