

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: NICK SEKICH UNIT B 01			
Project:COLORADO-WELD-NAD83-UTM13		Site:NICK SEKICH UNIT B 01	Rig Name No:BASIC 1509/1509
Event: ABANDONMENT		Start Date: 4/21/2014	End Date: Spud Date: 12/16/1974
Active Datum: RKB @4,905.99usft (above Mean Sea Level)		UWI: NW/NE/0/3/N/67/W/19/0/0/6/PM/N/1,250.00/E/0/0/0/0	
Report No	Report Date	MD (usft)	24 Hr Summary
1	04/21/2014		NDBOP. REMOVE OLD SURF HEAD. INSTALL NEW SURF H. RU R. IRON. WELD BELL NIPPLE. RD R. IRON. INSTALL 5K WH. NUBOP. TIH W/RETREAVING H. CIRC SAND, RELEASE RBP & POOH. RU WARRIOR W/L. RUN CIBP & SET @ 7560. DUMP 2 SX CEMENT ON TOP. RD W/L. SEE REMARKS:
2	04/22/2014		WAIT ON ORDERS. RU WARRIOR W/L. PERF SQ HOLES @ 6850 & 6450. 3 SPF .38". SET CIRC. @ 6860. RD W/L. TIH W/ CIRC STINGER. STING INTO. SUB UP. RU SANJEL. PUMP 1 BW AND PRESSURE UP COULD NOT PUMP THROUGH RETAINER AFTER SEVERAL ATTEMPTS. SEE REMARKS:
3	04/23/2014		RU POWER SWIVEL. SWIVEL BROKE. GOT REPAIR. DRILL CIRC & PUSH TO 6900. TOO. PU & TIH W/NEW CIRC. SET @ 6485. RU SANJEL. PUMP 5 BW, 120 SX 50/50 POZ G W/ 20% SILICA FL, 3% GEL, .1% SMS, .4% FL-52. MIX @ 13.5 PPG & 1.71 CF/SK. DISP W/23 BW. SEE REMARKS:
4	04/24/2014		WAIT ON W/L. RU WARRIOR W/L. PERF SQ HOLES @ 4240 & 3840. 3 SPF, .5 EHD, 120 PHASING. PU & TIH W/CIRC & SET @ 3870. RU SANJEL. PUMP 5 BW, 20 BBLS SMS. 5 BW, 225 SX "G" W/.25 PPS CELLO FL, .4% CD-32, .4% ASA-301. SEE REMARKS:
5	04/25/2014		SPOT TBG FLOAT. LD 25 JTS OF CSG. XO TO 2-3/8 EQUIP. TIH W/30 JTS @ 950. RU SANJEL. PUMP 310 SX TYPE III W/CELLO FLAKE & CaCL2. MIX @ 14.2 PPG & 1.53 CUFT/SK. DISP W/3.5 BW. LD 27 JTS. CIRC W/10 BW. RD SANJEL. LD TBG. SWI. SDFN.
6	04/28/2014		ND BOP & WH FLANGE. RU WARRIOR W/L. TAG TOC @ 103. SET CIBP @ 100'. RD WARRIOR W/L. RD PUMP. RDMO
7	05/22/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 75'. Filled casing stub with 30 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled.

REMARKS:

- 04/21/14 - LOAD & TEST CSG TO 1000. OK. SWI SDFN
- 04/22/14 - RD SANJEL. STING OUT OF CIRC. TOO. PU BIT & TIH TO RETAINER. SWI SDFN
- 04/23/14 - STING OUT OF CIRC. LD 18 JTS. CIRC W/70 BW. RD SANJEL. STD BACK 61 STDS LD REST OF TBG. SWI SDFN
- 04/24/14 - MIX @ 15.8 PPG & 1.15 CF/SK. DISP W/ 12 BW. STING OUT OF CIRC. LD 18 JTS. CIRC W/70 BW. RD SANJEL. STD BACK 15 STDS LD REST OF TBG. RIG UP WARRIOR W/L. RIH W/ JET CUT & CUT CSG @ 850. RD W/L. CIRC GAS OUT. NDBOP. XO TO 4.5 EQUIP. CHANGE OUT SURF HEADS. NUBOP. SWI SDFN