

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400519976

Date Received:

11/27/2013

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☐ COALBED ☐ OTHER Water Injection

Refiling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: PWD Federal

Well Number: 21-6-91

Name of Operator: DEJOUR ENERGY (USA) CORPORATION

COGCC Operator Number: 10301

Address: 1401 17TH STREET #850

City: DENVER State: CO Zip: 80202

Contact Name: Neyeska Mut

Phone: (303)296-3535

Fax: (303)296-3888

Email: ngmut@dejour.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: SWSE Sec: 21 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.508541

Longitude: -107.556063

Footage at Surface: 791 feet FNL/FSL FSL 1782 feet FEL/FWL FEL

Field Name: KOKOPELLI

Field Number: 47525

Ground Elevation: 7009.5

County: GARFIELD

GPS Data:

Date of Measurement: 04/12/2010 PDOP Reading: 3.0 Instrument Operator's Name: Kyle Tesky

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 657 FSL 2668 FEL 657 FEL 2668 FEL
Sec: 21 Twp: 6S Rng: 91W Sec: 21 Twp: 6S Rng: 91W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____

Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

The 80-acre tract is part of Federal Lease #COC66370. The proposed well is a produced water injection well and the radius of injection should not extend beyond the 80-acre tract boundaries.

Federal Lease #COC66370: 6th Meridian, Township 6 South, Range 91 West; Section 21: E2NE, SESW, AND SWSE; Section 22: SWNW, W2SW, and SESW; Section 25: SWSW; and Section 26: S2.

Total Acres in Described Lease: 680 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC66370

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 791 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4854 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 4854 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 448 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 700 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary _____ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-70		

DRILLING PROGRAM

Proposed Total Measured Depth: 9054 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 700 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule N/A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18	14	54	0	80	100	80	0
SURF	12+1/4	8+5/8	24	0	1500	800	1500	0
1ST	7+7/8	4+1/2	11.6	1300	9050	665	9050	1300

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments The original (approved) APD expires on January 5, 2014. Dejour plans to drill this well after the current expiration date and is refiling the APD for approval.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 426533

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Rick Obernolte

Title: Environmental Consultant Date: 11/27/2013 Email: rickobe1@aol.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/6/2014

Expiration Date: 06/05/2016

API NUMBER

05 045 21277 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE</p> <p>(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.</p> <p>(3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.</p> <p>(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.</p> <p>(5) CEMENT ON PRODUCTION CASING (4-1/2" FIRST STRING) MUST EXTEND INTO THE SURFACE CASING (MINIMUM 200' LAP ABOVE SURFACE CASING SHOE) TO PROVIDE ISOLATION OF THE MESAVERT GROUP AND ANY PORTION OF THE WASATCH FORMATION THAT IS NOT OTHERWISE COVERED BY SURFACE CASING. VERIFY PRODUCTION CASING CEMENT COVERAGE WITH A CBL.</p> <p>(6) APPROVAL OF THIS FORM DOES NOT AUTHORIZE INJECTION. AUTHORIZATION TO INJECT REQUIRES APPROVAL OF FORM 31 AND FORM 33.</p> <p>(7) BEFORE STIMULATING THE OBJECTIVE INJECTION FORMATION(S), COLLECT WATER SAMPLE(S) AND ANALYZE FOR TOTAL DISSOLVED SOLIDS. PRIOR APPROVAL OF FORM 4 IS REQUIRED FOR STEP RATE AND INJECTIVITY TESTS.</p>
--	--

Best Management Practices

No BMP/COA Type

Description

--	--

Applicable Policies and Notices to Operators

Mamm Creek Field Area Notice to Operators.
Piceance Rulison Field - Notice to Operators.
NW Colorado Notification Policy.
Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field).
Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400519976	FORM 2 SUBMITTED
400520062	DRILLING PLAN
400520063	DEVIATED DRILLING PLAN
400520065	WELL LOCATION PLAT
400558245	DIRECTIONAL DATA

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
UIC	Placed form In-Process. In telephone conversation today operator says they will be submitting new Form 31 and Form 33 later this week or early next week. Operator also says they will pay special attention to answering concerns about seals between injection zone and Williams Fork/Cameo Formation as mentioned in David Andrews comment on 3/5/2014. Injection expected to be into the Cozzette and Corcoran Formations.	3/3/2014 1:46:33 PM
Engineer	FORM PLACED ON HOLD. CONCERNS WITH OFFSET ILES PRODUCTION AND POTENTIAL FOR COMMUNICATION OF ILES INJECTED FLUIDS WITH OVERLYING WILLIAMS FORK PRODUCTION. WHAT IS THE PLANNED SEPARATION BETWEEN THE UPPERMOST ILES INJECTION PERFORATION AND THE BASE OF THE WILLIAMS FORK/CAMEO?	3/5/2014 8:50:10 AM
Permit	Final review completed on this water injection well. NO LGD comments.	2/20/2014 2:30:25 PM
LGD	pass, gdb	12/16/2013 12:28:10 PM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.	12/5/2013 2:19:50 PM
Permit	This form has passed completeness.	11/29/2013 1:11:45 PM

Total: 6 comment(s)