

FORM  
2  
Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
400619283

APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

Date Received:

TYPE OF WELL OIL  GAS  COALBED  OTHER \_\_\_\_\_

Refiling

ZONE TYPE SINGLE ZONE  MULTIPLE ZONES  COMMINGLE ZONES

Sidetrack

Well Name: Evans Well Number: 2-21H  
Name of Operator: EE3 LLC COGCC Operator Number: 10450  
Address: 4410 ARAPAHOE AVENUE #100  
City: BOULDER State: CO Zip: 80303  
Contact Name: Ann Stephens Phone: (303)928.7128 Fax: (303)218.5678  
Email: regulatory@petro-fs.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130007

WELL LOCATION INFORMATION

QtrQtr: NWNE Sec: 21 Twp: 7N Rng: 80W Meridian: 6

Latitude: 40.569663 Longitude: -106.375875

Footage at Surface: 204 feet FNL/FSL FNL 1919 feet FEL/FWL FEL

Field Name: WILDCAT Field Number: 99999

Ground Elevation: 8236 County: JACKSON

GPS Data:

Date of Measurement: 09/12/2013 PDOP Reading: 1.4 Instrument Operator's Name: RAS

If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL 610 FEL/FWL FNL 2049 FEL Bottom Hole: FNL/FSL FSL 600 FEL/FWL FSL 1980 FWL  
Sec: 21 Twp: 7N Rng: 80W Sec: 21 Twp: 7N Rng: 80W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee  State  Federal  Indian

The Surface Owner is:  is the mineral owner beneath the location.  
(check all that apply)  is committed to an Oil and Gas Lease.  
 has signed the Oil and Gas Lease.  
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee  State  Federal  Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 7 North, Range 80 West, 6th PM:  
Section 17: S/2  
Section 19: E/2  
Section 20: All  
Section 21: N/2, N/2S/2, S/2SW/4  
Section 22: W/2NW/4  
Section 24: E/2, E/2SW/4  
Section 25: N/2NE/4  
Section 29: N/2N/2, SW/4NW/4, NW/4SW/4  
Section 30: E/2  
Township 7 North, Range 79 West, 6th PM:  
Section 19: Lots 2(36.91), 3(36.79), 4(36.66), SE/4NW/4, NW/4NE/4, NE/4SW/4, W/2SE/4, SE/4SE/4  
Section 20: SW/4SW/4  
Section 30: Lot 1 (36.57)

Total Acres in Described Lease: 3387 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 204 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet  
Building Unit: 5280 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 5134 Feet  
Above Ground Utility: 5280 Feet  
Railroad: 5280 Feet  
Property Line: 204 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 2848 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

The closest wellbore permitted or completed in the same formation is the Castle 3-30H, API 05-057-06503, approx 2848' SW.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	531-2	640	All

## DRILLING PROGRAM

Proposed Total Measured Depth: 12796 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 2848 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

The cuttings will be remediated onsite using EcoSponge.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1400	900	1400	0
1ST	8+3/4	5+1/2	20	0	12796	1700	12796	0

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application?

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Ann Stephens

Title: Regulatory Manager Date: \_\_\_\_\_ Email: regulatory@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

**API NUMBER**

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

## Best Management Practices

No	<u>BMP/COA Type</u>	<u>Description</u>
1	Planning	A multi-well site will be used for directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources. Pits are not planned for this location.
2	General Housekeeping	Fence the well site after drilling to restrict public and wildlife access. Keep well site location, road and the pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds and implement dust control, as needed. Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by operator, its employees, or contractors cross through fences on the leased premises.

3	Wildlife	<p>Where oil and gas activities must occur within the greater sage grouse leks or within other mapped greater sage grouse breeding or summer habitat, Operator will conduct these activities outside the period between March 1 and June 30.</p> <p>Restrict post development well site visitations to portions of the day between 9:00 am and 4:00 pm during the lekking season (March 1 to May 15).</p> <p>Use hospital grade mufflers for compressors, pump jacks or other motors necessary to run operations at the site. Mufflers will be pointed upward to dissipate potential vibration.</p> <p>Establish company guidelines to minimize wildlife mortality from vehicle collisions on roads. Slow speeds and increased awareness among employees and contractors should lessen impacts to wildlife.</p> <p>Install and utilize bear-proof dumpsters and trash receptacles for all food-related trash on location, following COGCC Rule 1204.a.(1).</p>
4	Storm Water/Erosion Control	<p>Use water bars and other measures to prevent erosion and non-source pollution. Implement and maintain BMPs to control storm water runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation.</p> <p>Co-locate gas and water gathering lines whenever feasible and mitigate any erosion problems that arise due to the construction of any pipeline(s).</p>
5	Construction	<p>Remove only the minimum amount of vegetation necessary for the construction of roads and facilities.</p> <p>Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation.</p> <p>No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.</p>
6	Noise mitigation	<p>The drill site is far enough away from any building units that noise mitigation will not be required.</p>
7	Drilling/Completion Operations	<p>A closed-loop drilling mud system will be used to preclude the use of an earthen reserve pit when available. Light Sources will likewise be directed downwards and away from occupied structures, where possible. Once the drilling and completion rigs leave the site, there will be no permanently installed lighting on site.</p>
8	Interim Reclamation	<p>Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p>
9	Final Reclamation	<p>All surface restoration shall be accomplished to the satisfaction of Owner.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p> <p>Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).</p>

Total: 9 comment(s)

### **Attachment Check List**

<b>Att Doc Num</b>	<b>Name</b>
400619659	WELL LOCATION PLAT
400619667	DIRECTIONAL DATA
400622359	DEVIATED DRILLING PLAN
400623432	SURFACE AGRMT/SURETY

Total Attach: 4 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)