

FORM  
2

Rev  
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400557347

Date Received:

03/25/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refiling ☒

ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒

Sidetrack ☐

Well Name: JOLLEY

Well Number: KP 342-18

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

Contact Name: GINA RANDOLPH

Phone: (303)260-4509

Fax: (303)629-8268

Email: GINA.RANDOLPH@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: \_\_\_\_\_

WELL LOCATION INFORMATION

QtrQtr: NWSW Sec: 17 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.526024

Longitude: -107.587083

Footage at Surface: 2056 feet FNL/FSL FSL 215 feet FEL/FWL FWL

Field Name: KOKOPELLI

Field Number: 47525

Ground Elevation: 6202

County: GARFIELD

GPS Data:

Date of Measurement: 01/12/2012 PDOP Reading: 2.4 Instrument Operator's Name: J. KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

1614 FNL 648 FEL 1614 FNL 648 FEL  
Sec: 18 Twp: 6S Rng: 91W Sec: 18 Twp: 6S Rng: 91W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply)

☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_

Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

### LEASE PREVIOUSLY SUBMITTED

Total Acres in Described Lease: 1200 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian  
Federal or State Lease # COC51146  
Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 1614 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4645 Feet  
Building Unit: 4812 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 5280 Feet  
Above Ground Utility: 257 Feet  
Railroad: 5280 Feet  
Property Line: 215 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 313 Feet  
Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)  
Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| WILLIAMS FORK-ILES     | WFILS          | 513-4                   |                               |                                      |

## DRILLING PROGRAM

Proposed Total Measured Depth: 7780 Feet  
Distance to nearest permitted or existing wellbore penetrating objective formation: 313 Feet (Including plugged wells)  
Will a closed-loop drilling system be used? Yes  
Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)  
Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drlg fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted?

Reuse Facility ID:  or Document Number:

## CASING PROGRAM

| Casing Type | Size of Hole | Size of Casing | Wt/Ft  | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|--------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR   | 26           | 18             | 47.44# | 0             | 70            | 100       | 70      | 0       |
| SURF        | 13+1/2       | 9+5/8          | 32.3#  | 0             | 1434          | 373       | 1434    | 0       |
| 1ST         | 7+7/8        | 4+1/2          | 11.6#  | 0             | 7780          | 953       | 7780    |         |

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

CLOSED LOOP, SEE WILLIAMS MASTER APD.  
I certify that there have been no changes to the location.  
I certify that there have been no changes on land use, lease description.  
The pad has been built.  
No pit will be used.  
There will be no additional surface disturbance.  
The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).  
The location is not within a wildlife Restricted Surface Occupancy Area.

Previously approved Form 2A expires on April 5, 2015 (Doc. # 400248781).

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 419675

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: GINA RANDOLPH

Title: PERMIT TECH II Date: 3/25/2014 Email: GINA.RANDOLPH@WPXENE

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/14/2014

Expiration Date: 06/13/2016

**API NUMBER**

05 045 21465 00

## **Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### **COA Type**

### **Description**

|  |  |
|--|--|
|  | <p>(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE.</p> <p>(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.</p> <p>(3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED, WITH THE FOLLOWING EXCEPTION: ALL FIELD NOTICE REQUIREMENTS SPECIFIED IN THIS NOTICE TO OPERATORS ARE SUPERSEDED BY THE REQUIREMENTS OF THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY (SEE CONDITION OF APPROVAL #1). SEE ATTACHED NOTICE.</p> <p>(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)).</p> <p>(5) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFICATION BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE MAMM CREEK FIELD NOTICE TO OPERATORS.</p> |
|  | Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.   |

## **Best Management Practices**

### **No BMP/COA Type**

### **Description**

|  |  |  |
|--|--|--|
|  |  |  |
|--|--|--|

## **Applicable Policies and Notices to Operators**

|  |
|--|
| Mamm Creek Field Area Notice to Operators.   |
| Piceance Rulison Field - Notice to Operators.  |
| NW Colorado Notification Policy.   |
| Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field). |
| Notice Concerning Operating Requirements for Wildlife Protection.  |

## **Attachment Check List**

| <u>Att Doc Num</u> | <u>Name</u>        |
|--------------------|--------------------|
| 400557347          | FORM 2 SUBMITTED   |
| 400557718          | WELL LOCATION PLAT |
| 400557720          | LOCATION DRAWING   |

Total Attach: 3 Files

### General Comments

| <u>User Group</u> | <u>Comment</u>  | <u>Comment Date</u>      |
|-------------------|---|--------------------------|
| Final Review      | Corrected right to construct: changed from Oil and Gas Lease to Surface Use Agreement, per previously approved APD for this well and Location Assessment for this location.   | 6/14/2014<br>9:45:20 AM  |
| Permit            | Final review completed on this refile. No LGD comments.   | 3/9/2014 8:42:23<br>AM   |
| Permit            | There are four producers on the pad. The approved 2A expires 4/5/2015.  | 3/9/2014 8:41:34<br>AM   |
| Permit            | There are four producers on the pad. The approved 2A expires 4/5/2015.  | 3/9/2014 8:41:19<br>AM   |
| LGD               | pass, gdb   | 4/11/2014<br>11:06:13 AM |
| Engineer          | THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELLS WITHIN 1-MILE SHOW DEPTHS OF 240 FEET DEEP.<br><br>Evaluated existing offset wells within 1,500 feet of this wellbore. No mitigation required. | 3/31/2014<br>10:31:44 AM |
| Permit            | Passed completeness.  | 3/26/2014<br>12:32:19 PM |
| Permit            | Operator requested inserting refile statements.   | 3/26/2014<br>12:31:52 PM |

Total: 8 comment(s)