

After Replug Schematic:

10-3/4 32.7# H40 Surface  
Set @ 292' MD

5 1/2" 15.5# J-55 Prod Csg  
Set @ 6790' and cut off @ '2630

7 7/8" OH  
To 6840' MD

~95' cement @ top of surface csg

50 sx cement backside of surface casing

50 sx balanced plug from 342' to 228'

50 sx balanced plug from 2500' to 2344'

5 sx cement 6660 to 6695'

8 Perforations  
6700'-6702'

