

# DAVIS 1-10

660 FNL660 FEL NENE 10 5N 61W 6th PM  
Lat 40.421327 Long -104.187653 (from footages)  
Weld County, Colorado  
API #05-123-11568

Spud date 1/2/1984

4729 KB  
4718 GL

8.625", 24#/ft Wt, Grade, 164', 12.25" hole  
Cemented to surface w/ 170 sx.

Water N/A  
(Within 1 mile radius)

Plugging Summary  
Well was plugged January 9, 1984  
25 sxs cement plug at base of surface casing  
10 sxs cement plug at surface  
25 sxs across D-Sand (6,690'-6780')

As found in well:  
DAVIS 1-10

TOC N/A '

Niobrara 6030 '

Fort Hayes 6295 '

D Sand 6731 '

J Sand 6794 '

7 7/8" hole  
No Prod Casing

PBTD -- ft  
TD 6895 ft 1/8/1984

Updated 5/14/2014 oc