

Furrow 1-18

660 FSL660 FWL SWSW 18 5N 61W 6th PM
Lat 40.395477 Long -104.259345 (from footages)
Weld County, Colorado
API #05-123-05181

Spud date 4/28/1956

4552' KB
4542' GL

10.75", 32#/ft Wt, Grade, 106', 12.25" hole
Cemented to surface w/ 150 sx.

OH Plug from 695' to Surface

Water N/A
(Within 1 mile radius)

Plugging Summary
Well plugged April , 2014
4/16/2014 - 1st plug set from 4032 w/200 sks
2nd plug set from 2400 - 1900 w/200sks
4/17/2014 - 3rd plug set from 695 - top w/440 sks

As found in well:
Furrow 1-18

OH plug 4032' to 1900'

TOC N/A '

Parkman 3197 '
Niobrara 6086 '

Codell 6258 '

D Sand 6638 '
J Sand 6700

7 7/8" hole
No Prod Casing

TD 6816 ft 5/10/1956

Updated 5/29/2014 oc