

Weld County, Colorado, Northern Part

47—Otero sandy loam, 3 to 9 percent slopes

Map Unit Setting

Elevation: 4,500 to 5,500 feet

Mean annual precipitation: 12 to 15 inches

Mean annual air temperature: 48 to 52 degrees F

Frost-free period: 130 to 180 days

Map Unit Composition

Otero and similar soils: 85 percent

Minor components: 15 percent

Description of Otero

Setting

Landform: Fans, plains

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Calcareous loamy alluvium and/or colluvium

Typical profile

H1 - 0 to 5 inches: moderately alkaline, sandy loam

H2 - 0 to 5 inches: moderately alkaline, sandy loam

H2 - 0 to 5 inches: moderately alkaline, sandy loam

Properties and qualities

Slope: 3 to 9 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat):

Moderately high to high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 10 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 4.0 mmhos/cm)

Available water storage in profile: Very high (about 14.8 inches)

Interpretive groups

Farmland classification: Not prime farmland

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: B

Ecological site: Sandy Plains (R067BY024CO)

Minor Components

Stoneham

Percent of map unit: 7 percent

Kim

Percent of map unit: 3 percent

Bushman

Percent of map unit: 3 percent

Mitchell

Percent of map unit: 2 percent

Data Source Information

Soil Survey Area: Weld County, Colorado, Northern Part
Survey Area Data: Version 9, Dec 23, 2013