

Crissy Venturo

From: Diana Burn - DNR <diana.burn@state.co.us>
Sent: Wednesday, June 18, 2014 9:24 AM
To: Chad Fitzgerald
Cc: Dirk Sutphin - DNR; Barbara Westerdale - DNR
Subject: RE: Razor 26L 3503A Unplanned Sidetrack 123-37991

Please proceed as proposed.

Thanks,
Diana

From: Chad Fitzgerald [mailto:chad.fitzgerald@whiting.com]
Sent: Wednesday, June 18, 2014 9:14 AM
To: diana.burn@state.co.us
Subject: Razor 26L 3503A Unplanned Sidetrack

Sidetrack Request

RAZOR 26L-3503A – API: 05-123-37991-00

PROPOSED OR COMPLETED OPERATIONS:

Diana,

While drilling in the lateral we were high in zone and approaching the Sharon Springs and the hole started sluffing in. We had to trip out of the hole to change out a MWD tool. While tripping back in the hole the drum brake failed on the rig and we had to wait on a new one to be shipped from Houston. We were out of the hole for about 36 hours. When tripping back to bottom we were 150' off bottom and had to ream the hole due to the hole depleted hole conditions and failed the motor. Due to the hole conditions of that last 150' we feel we will not be able to run our production liner and request to sidetrack lower in Niobrara A zone. We will be running a cemented production liner.

- **TOTAL DEPTH REACHED:**

- 7,550' (MD) 5582' (TVD)

- **CASING:**

- **SURFACE CASING:**

- **SIZE:** 9.625" 36PPF

- **DEPTH:** 1,528 MD 1524' TVD

- **PRODUCTION CASING:**

- **SIZE:** 7.0" 29 PPF J-55 LTC

- **DEPTH:** 6,006' MD 5,600' TVD

- **SIDETRACK PROCEDURE AND PLUG BACK DEPTHS:**

- No plug will be set in horizontal bore; Plan to trip in with our directional assembly and time drill to go on the low side of the current wellbore.

- **SIDETRACK KICK OFF POINT:**

- 7000' (MD) 5596' (TVD)

- **BHL TARGET FOR SIDETRACK HOLE:**

- (SAME TARGET) 600' FSL AND 825'FWL S35-T10N-R58W

Chad Fitzgerald

Drilling Engineer

Whiting Petroleum Corporation

and its wholly owned subsidiary

Whiting Oil and Gas Corporation

1700 Broadway, Suite 2300

Denver, CO 80290

Direct (303) 495-6756

Cell (303) 514-5076

chad.fitzgerald@whiting.com

www.whiting.com

The information contained in this message may be privileged and confidential and protected from disclosure. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is strictly prohibited. If you have received this communication in error, please notify us immediately by replying to this message and deleting it from your computer.