

US ROCKIES REGION

Anadarko Daily Summary Report

Well: PERRIN HELEN R GU #1

Project: COLORADO-WELD-NAD83-UTM13

Site: PERRIN HELEN R GU #1

Rig Name No: LEED/724

Event: ABANDONMENT

Start Date: 4/7/2014

End Date: 5/28/2014

Spud Date: 5/1/1975

Active Datum: RKB @5,055.99usft (above Mean Sea Level)

UWI: 0/2/N/67/W/29/0/SWSE/6/0/0/0/0/0/0

| Report No | Report Date | MD (usft) | 24 Hr Summary |
|-----------|-------------|-----------|---|
| 1 | 04/07/2014 | | MIRU Leed 724 RU pump & tank TP:400,CP:400,SP:0. Blew down well & controlled it, NDWH NUBOP RU work floor TOO H SB 220 jts LD 44 jts on trailer MIRU Warrior WL RIH G-ring J-basket to 8100' set 4.5 CIBP w/CMT cap @ 8060' set 4.5 CIBP w/CMT cap @ 7625' RDWL |
| 2 | 04/08/2014 | | RU Warrior WL run CBL from 7400' up to surface found good CMT from 7400' to 7320', 4970' to 4870' and from 4350' to 4160' RDWL RU SL truck run Gyro from 7600' up to surface. RUWL shot SQ holes @ 7260' & 6860' RDWL RU H-S tester PU CICR TIH tested tgb in |
| 3 | 04/09/2014 | | Loaded tbg established circulation 2 bbl/min @ 900 psi. MIRU Baker Huges pumped 150 sks 50/50 poz G 13.5 ppg, 1.71 cf/sk RD Baker TOO H RU Warrior WL shot SQ holes @ 5200' & 5000' RDWL TIH CICR circulated well could not set CICR TOO H LD CICR TIH new CICR |
| 4 | 04/10/2014 | | RU Pioneer WL RIH shot SQ holes @ 4400' & 4600' RDWL TIH CICR set it @ 4440' RU Baker pumped 20 bbls of SMS & 200 sks class "G" CMT 15.8 ppg, 1.15 cf/sk RD Baker TOO H RU Pioneer WL shot SQ holes @ 600' & 1370' RDWL TIH CICR set it @ 618' RU Baker |
| 5 | 04/11/2014 | | TIH tag TOC @ 210 RU Baker pumped 23 sks Type III CMT 14.0 ppg, 1.53 cf/sk RD Baker TOO H WOC 4 hrs TIH tag TOC @ 96' LD tbg RU Warrior WL RIH set 4 1/2 CIBP @ 90' RDWL PT CIBP to 1000 psi 15 mins held good NDBOP RDMO Leed 724. |
| 6 | 05/28/2014 | | TIME : 15:00, ROUTE : W16, WINS: 74835, PROJECT TYPE: P&A, PROD: CD/J, BATT#: 34002031, GATHERER: KMG, STATION: 008191, LINE : 16-220-4, COMMENTS: P&A'd OFFLINE. |

COMMENTS:

04/07/14 - LOADED WELL SWI SDFN

04/08/14 - **(DID GYRO SURVEY REQUESTED BY JAMES JARAMILLO)** RD TESTER SET CICR @ 6902' W/224 JTS SWI SDFN

04/09/14 - SET IT @ 5033' RU BAKER PUMPED 20 BBLs SMS & 220 sks OFCLASS "G" CMT 15.8 ppg, 1.15 cf/sk RD BAKER TOO H SWI SDFN.

04/10/14 - PUMPED 470 sks TYPE III CMT RD BAKER TOO H SWI SDFN