

FORM  
5  
Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:  
400597981

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 96155  
2. Name of Operator: WHITING OIL AND GAS CORPORATION  
3. Address: 1700 BROADWAY STE 2300  
City: DENVER State: CO Zip: 80290  
4. Contact Name: Elvera Berryman  
Phone: (303) 390-4221  
Fax: (303) 390-1598

5. API Number 05-123-38346-00  
6. County: WELD  
7. Well Name: Razor Federal  
Well Number: 26J-3511A  
8. Location: QtrQtr: NWSE Section: 26 Township: 10N Range: 58W Meridian: 6  
Footage at surface: Distance: 2326 feet Direction: FSL Distance: 1947 feet Direction: FEL  
As Drilled Latitude: 40.808744 As Drilled Longitude: -103.829602

GPS Data:  
Date of Measurement: 01/30/2014 PDOP Reading: 2.0 GPS Instrument Operator's Name: Larry D. Brown

\*\* If directional footage at Top of Prod. Zone Dist.: 1471 feet. Direction: FSL Dist.: 1740 feet. Direction: FEL  
Sec: 26 Twp: 10 Rng: 58

\*\* If directional footage at Bottom Hole Dist.: 638 feet. Direction: FSL Dist.: 1813 feet. Direction: FEL  
Sec: 35 Twp: 10 Rng: 58

9. Field Name: WILDCAT 10. Field Number: 99999  
11. Federal, Indian or State Lease Number: COC075023

12. Spud Date: (when the 1st bit hit the dirt) 04/22/2014 13. Date TD: 05/02/2014 14. Date Casing Set or D&A: 05/03/2014

15. Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 12200 TVD\*\* 5598 17 Plug Back Total Depth MD 12200 TVD\*\* 5598

18. Elevations GR 4726 KB 4743  
One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:  
LWD, MUD, CBL, Note OH logs run on RAZOR 26J-2633L

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20	16	84	0	97		0	97	VISU
SURF	13+1/2	9+5/8	36	0	1,536	455	0	1,536	VISU
1ST	8+3/4	7	29	0	6,024	816	484	6,024	CBL
1ST LINER	6	4+1/2	11.60	4859	12,190	456	4,859	12,190	VISU

### STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	1,691		<input type="checkbox"/>	<input type="checkbox"/>	
HYGIENE	3,513		<input type="checkbox"/>	<input type="checkbox"/>	
SHARON SPRINGS	5,766		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	5,787		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Elvera Berryman

Title: Engineer Tech

Date: \_\_\_\_\_

Email: elvera.berryman@whiting.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400627981	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400627975	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400627976	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400627988	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400628718	PDF-Measurement/Logging While Drilling	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400628719	LAS-Measurement/Logging While Drilling	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400628720	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)