



ESTIMATED EARTHWORK QUANTITIES (cy)

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	28150	24150	4000	0
PIT	0			0
TOTALS	28150	24150	4000	0

REVISED: 6/24/14

SCALE: 1" = 80'
DATE: 6/11/14
PLAT: 2 of 7
PROJECT: Valley
DFT: cs

*NOTE:

- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 2.) Topsoil Volume Based on 12" Soil Depth.
- 3.) Total Disturbed Area = ±4.24 ac.

Construction Plan Prepared for:
WPXENERGY WPX Energy Rocky Mountain, LLC

GM 13-33 Drill Pad - Plat 2

Facility Drawing Layout

136 East Third Street
Rifle, Colorado 81650
Ph. (970) 625-2720
Fax (970) 625-2773



BOOKCLIFF
Survey Services, Inc.