

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400597619

Date Received:

04/29/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Lippert

Well Number: 14-05 1S44W

Name of Operator: AUGUSTUS ENERGY RESOURCES LLC

COGCC Operator Number: 10489

Address: 36695 HWY 385

City: WRAY State: CO Zip: 80758

Contact Name: Loni Davis

Phone: (970)332-3585

Fax: (970)332-3587

Email: ldavis@augustusenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130106

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 5 Twp: 1S Rng: 44w Meridian: 6

Latitude: 39.992271

Longitude: -102.334723

Footage at Surface: 311 feet FNL/FSL FSL 606 feet FEL/FWL FWL

Field Name: VERNON

Field Number: 86500

Ground Elevation: 3985

County: YUMA

GPS Data:

Date of Measurement: 04/25/2014 PDOP Reading: 1.4 Instrument Operator's Name: John Thompson

If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1-S-R45W Sec 05: SW/4

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 311 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1142 Feet
Building Unit: 1142 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 297 Feet
Above Ground Utility: 284 Feet
Railroad: 5280 Feet
Property Line: 297 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 717 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 311 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

The nearest well Dtereding 11-08 API # 05-125-10977 was spud 10/17/2007.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	315-3	160	SW/4

DRILLING PROGRAM

Proposed Total Measured Depth: 2545 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 717 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: UIC Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Drilling pit

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7	17	0	430	200	430	0
1ST	6+1/4	4+1/2	10.5	0	2545	100	2545	0

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Loni Davis

Title: Oper. Acctg & Reg Spec Date: 4/29/2014 Email: ldavis@augustusenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 6/28/2014
Expiration Date: 06/27/2016

API NUMBER

05 125 12085 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	1) Provide 48 hour notice prior to spud via electronic Form 42. 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (430' minimum - as proposed without prior approval of lesser amount). 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. 5) Supply mud report showing chlorides, representative of conditions at TD, with Form 5.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	<p>Best Management Practices Southern Yuma County, Colorado</p> <p>To address construction during drilling and all other operations associated with Oil and Gas development throughout Southern Yuma County, Colorado area StormWater Management Plans(SWMP) are in place and in compliance with the Colorado Department of Health and Environment (CDPHE) under Permit # COR-039920.</p> <p>Best Management Practices (BMP's) will be reviewed and maintained prior to, during and after construction of drilling site, laying of flowlines, installation of surface equipment and reclamation of site. Each location's BMP's will vary according to terrain and phase of construction and will be implemented in accordance to SWMP.</p> <p>Regular location inspections will be performed and any BMP's not effectively working will be documented and resolved in a timely manner.</p> <p>Spill Prevention, Control and Countermeasures will be implemented. Should any spills occur they will be cleaned up immediately and effectively to minimize any integration with storm water runoff. General good housekeeping practices will be performed to keep spills at a minimum.</p>

Total: 1 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400597619	FORM 2 SUBMITTED
400597731	WELL LOCATION PLAT
400597734	TOPO MAP
400597737	30 DAY NOTICE LETTER
400597743	SURFACE AGRMT/SURETY

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed; no LGD or public comment received.	6/27/2014 6:13:58 AM
Engineer	5/9/14- Received information from operator that mud chlorides will be maintained around 12,000 ppm.	5/19/2014 2:18:44 PM
Engineer	Requested information on planned mud salinity.	5/6/2014 4:41:23 PM
Permit	This well and its location are governed by Rule 318.B (effective date of 318.B. is 7/30/2006) and not Cause 315-3 and its associated well count and setback.	5/5/2014 7:32:42 AM
Permit	Passed completeness	4/30/2014 4:32:38 PM
Permit	Return to draft; Plugging and Abandonment Bond Surety ID number is not valid	4/30/2014 2:52:27 PM

Total: 6 comment(s)