

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

1813827

Date Received:

06/24/2009

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: GREG DAVIS Phone: (303)606-4071 Fax: (303)629-8272

Email: GREG.J.DAVIS@WILLIAMS.COM

7. Well Name: SAVAGE Well Number: RWF 541-35

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8171

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 35 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.487185 Longitude: -107.853217

Footage at Surface: 716 feet FNL/FSL 2049 feet FEL/FWL  
FNL FEL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 5442 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/23/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. KIRKPATRICK

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
1311 FNL 196 FEL 1311 FNL 196 FEL  
Sec: 35 Twp: 6S Rng: 94W Sec: 35 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 260 ft

18. Distance to nearest property line: 554 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 329 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| WILLIAMS FORK          | WMFK           | 139-66                  | 640                           | ALL                                  |

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC07506

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6S-R94W; SEC 35: NW, E/2E/2, SWNE, NESW; SEC 36; LOTS 1.2.3.4; T7S-R94W; SEC1: LOTS 3,4, S/2NW; SEC 2: LOTS 1.3.4 S/2N/2, SEC 3: LOTS 1,2, S/2NE

25. Distance to Nearest Mineral Lease Line: 1144 ft

26. Total Acres in Lease: 1167

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP/RE-USE

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR   | 24           | 18             | 48    |               | 45            |           | 45      | 0       |
| SURF        | 13+1/2       | 9+5/8          | 32.3  |               | 1734          |           | 1734    | 0       |
| 1ST         | 7+7/8        | 4+1/2          | 11.6  |               | 8171          |           | 8171    |         |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CLOSED LOOP. SEE WILLIAMS PRODUCITON RMT COMPANY MASTER APD, STANDARD OPERATING PRACTICES VERSION: 4/27/06

34. Location ID: 323908

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: GREG DAVIS

Title: SUPERVISOR PERMITS Date: 6/25/2009 Email: GREG.J.DAVIS@WILLIAMS.C

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/27/2009

#### API NUMBER

05 045 18758 00

Permit Number: Expiration Date: 9/26/2010

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Description**

NO CONDITIONS FOUND

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us

GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

CEMENT-TOP VERIFICATION BY CBL REQUIRED.

THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 250 FEET DEEP.

**Attachment Check List**

| <b><u>Att Doc Num</u></b> | <b><u>Name</u></b>     |
|---------------------------|------------------------|
| 1711051                   | LOCATION PICTURES      |
| 1711052                   | LOCATION PICTURES      |
| 1711053                   | LOCATION PICTURES      |
| 1711054                   | WELL LOCATION PLAT     |
| 1711055                   | TOPO MAP               |
| 1711056                   | SURFACE AGRMT/SURETY   |
| 1711057                   | DEVIATED DRILLING PLAN |
| 1711058                   | FED. DRILLING PERMIT   |
| 1711059                   | DRILLING PLAN          |
| 1813827                   | APD APPROVED           |
| 400007215                 | APD ORIG & 1 COPY      |

Total Attach: 11 Files

**General Comments**

| <b><u>User Group</u></b> | <b><u>Comment</u></b> | <b><u>Comment Date</u></b> |
|--------------------------|-----------------------|----------------------------|
|                          |                       |                            |

Total: 0 comment(s)

**Best Management Practices**

| <b><u>No</u></b> | <b><u>BMP/COA Type</u></b> | <b><u>Description</u></b> |
|------------------|----------------------------|---------------------------|
|                  |                            |                           |