

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400620250

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: TOMPKINS

Well Number: 32C-08-07-95

Name of Operator: URSA OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1050 17TH STREET #2400

City: DENVER

State: CO

Zip: 80265

Contact Name: JENNIFER LIND

Phone: (720)508-8362

Fax: ()

Email: JLIND@URSARESOURCES.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120125

WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 5 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.459962

Longitude: -108.013916

Footage at Surface: 200 feet FNL/FSL FSL 572 feet FEL/FWL FEL

Field Name: PARACHUTE

Field Number: 67350

Ground Elevation: 5528

County: GARFIELD

GPS Data:

Date of Measurement: 04/22/2014 PDOP Reading: 1.7 Instrument Operator's Name: HOFFMANN

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FNL 1980 FEL FEL/FWL FEL
 2090 FNL 1980 FEL 2090 FNL 1980 FEL
 Sec: 8 Twp: 7S Rng: 95W Sec: 8 Twp: 7S Rng: 95W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply)

☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

A PORTION OF THE N/2 OF SEC.8-T7S-R95W, SEE ATTACHED MINERAL LEASE MAP.

Total Acres in Described Lease: 268 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 35 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 468 Feet
Building Unit: 468 Feet
High Occupancy Building Unit: 5258 Feet
Designated Outside Activity Area: 528 Feet
Public Road: 223 Feet
Above Ground Utility: 215 Feet
Railroad: 5003 Feet
Property Line: 201 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☒ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 04/29/2014

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 2479 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 516 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	440-70	320	N/2

DRILLING PROGRAM

Proposed Total Measured Depth: 7698 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 2479 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

If cuttings meet Table 910 they will be beneficially reused.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	84	0	60	111	60	0
SURF	12+1/4	8+5/8	32	0	1843	380	1843	0
1ST	7+7/8	4+1/2	11.6	0	7698	494	7698	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

First String / Production cement will be > 500 feet above TOG. Please see attached plat for reference to cultural setbacks. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the existing Battlement Mesa Energy Partners #PA 434-5 (WPX well, API 05-045-15042).

Pre-application Notice / Buffer Zone Notice was sent to building unit owners within 1000' of the location on 4/29/14. The building unit owners within 1000' have waived all future notification requirements. Pre-application certification and signed notification waivers are attached to the associated Tompkins Pad Form 2A (Doc #400607816).

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: _____ Email: JLIND@URSARESOURCES.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Best Management Practices**No BMP/COA Type****Description**

--	--

Attachment Check List**Att Doc Num****Name**

400620257	WELL LOCATION PLAT
400620258	DEVIATED DRILLING PLAN
400620458	DIRECTIONAL DATA
400633692	SURFACE AGRMT/SURETY
400636703	MINERAL LEASE MAP

Total Attach: 5 Files

General Comments**User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)