

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400587268

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

04/17/2014

Well Name: SRC MARKHAM

Well Number: 31-16-9NHZ

Name of Operator: SYNERGY RESOURCES CORPORATION

COGCC Operator Number: 10311

Address: 20203 HIGHWAY 60

City: PLATTEVILLE

State: CO

Zip: 80651

Contact Name: Paul Gottlob

Phone: (720)420-5747

Fax: ()

Email: paul.gottlob@iptenergyservices.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090043

WELL LOCATION INFORMATION

QtrQtr: SENW Sec: 16 Twp: 4N Rng: 68W Meridian: 6

Latitude: 40.313924

Longitude: -105.010428

Footage at Surface: 2440 feet FNL/FSL FNL 2054 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4964

County: WELD

GPS Data:

Date of Measurement: 02/24/2014

PDOP Reading: 1.3

Instrument Operator's Name: Aaron A. Demo

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
2198 FNL 1800 FEL 460 FNL 1800 FEL
Sec: 16 Twp: 4N Rng: 68W Sec: 9 Twp: 4N Rng: 68W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

E/2 of NW/4, W/2 of NE/4 Sec 16 4N 68W
NE/4 of Sec. 16 is State Land Board Minerals #2486.12.

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # 2486.12

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1068 Feet
Building Unit: 1068 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 2017 Feet
Above Ground Utility: 1887 Feet
Railroad: 5280 Feet
Property Line: 215 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 420 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Spacing Unit: All Sec 9-T4N-R68W & N/2 Sec 16=T4N-R68W

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		960	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 13865 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 420 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☐ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Drilling Fluids & Cuttings will be off-site at Land Application location to be determined - a permitted location will be in place prior to use.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	550	290	550	0
1ST	8+3/4	7+0/0	26	0	6812	583	6812	3000
1ST LINER	6+1/8	4+1/2	11.6	6612	13865			

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Paul Gottlob

Title: Regulatory & Eng. Tech. Date: 4/17/2014 Email: paul.gottlob@iptenergyservices

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  _____ Director of COGCC Date: 7/6/2014

Expiration Date: 07/05/2016

API NUMBER

05 123 39825 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
	Operator acknowledges the proximity of the listed non-operated well: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. MARKHAM 1 (API NO 123-11077)
	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from the bottom of the production casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Planning	Multi-well Pads. It is a multi-well pad located in a manner which allows for resource extraction while maintaining the highest distances possible from the offsetting residential areas.
2	Traffic control	Access roads. The access road will be constructed to accommodate local emergency vehicles. This road will be maintained for access at all times.
3	General Housekeeping	Fencing requirements. A permanent fencing plan will be reviewed by the surface owner, & the applicant.
4	General Housekeeping	Removal of surface trash. All trash, debris and material not intrinsic to the operation of the oil and gas facility shall be removed and legally disposed of as is applicable.
5	Material Handling and Spill Prevention	Leak Detection Plan. Pumper will visit the location daily and visually inspect all tanks and fittings for leaks. Additionally, monthly documented SPCCP inspections are conducted pursuant to 40 CFR §112.
6	Material Handling and Spill Prevention	Berm construction. Tank berms shall be constructed of steel rings with a synthetic or engineered liner and designed to contain 150% of the capacity of the largest tank. All berms will be visually checked periodically to ensure proper working condition.
7	Material Handling and Spill Prevention	Load-lines. All load-lines shall be bull-plugged or capped.
8	Material Handling and Spill Prevention	Tank specifications. Tanks will be designed, constructed and maintained in accordance with NFPA Code 30. The tanks are visually inspected once a day for issues, and recorded inspections are conducted once a month.

9	Noise mitigation	Lighting abatement measures shall be implemented, including the installation lighting shield devices on all of the more conspicuous lights, low density sodium lighting where practicable; and rig shrouding is not believed necessary as this is an industrial area and the only building unit within 1,000' is owned by the operator, however, at its election the operator may install temporary engineering controls consisting of perimeter sound walls shall be used on the location during drilling and completion activities to provide noise relief. Permanent equipment on location shall be muffled to reduce noise, or shall be appropriately buffered.
10	Drilling/Completion Operations	Closed Loop Drilling Systems – Pit Restrictions. Not applicable; a closed-loop system will be used for drilling.
11	Drilling/Completion Operations	Green Completions – Emission Control Systems. Test separators and associated flow lines and sand traps shall be installed on-site to accommodate Green completions techniques pursuant to COGCC Rules. In the anticipated absence of a viable gas sales line, the flow-back gas shall be thermally oxidized in an emissions control device (ECD), which will be installed and kept in operable condition for least the first 90-days of production pursuant to CDPHE rules. This ECD shall have an adequate capacity for 1.5 times the largest flow-back within a 10 mile radius, will be flanged to route gas to other or permanent oxidizing equipment and shall be provided with the equipment needed to maintain combustion where non-combustible gases are present.
12	Drilling/Completion Operations	Blowout preventer equipment (“BOPE”). A double ram and annular preventer will be used during drilling. At least the drilling company shall have a valid well blowout prevention certifications.
13	Drilling/Completion Operations	BOPE for well servicing operations. Adequate BOP equipment shall be used. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.
14	Drilling/Completion Operations	Pit level indicators. Not applicable; a closed-loop system will be used and no pits shall be dug.
15	Drilling/Completion Operations	Drill stem tests. Not applicable; no Drill Stem tests are planned.
16	Drilling/Completion Operations	Control of fire hazards. All materials which are considered fire hazards shall be a minimum of 25' from the wellhead tanks or separators. Electrical equipment shall comply with API RP 500 and will comply with the current national electrical code. An emergency response plan has been generated for this site.
17	Drilling/Completion Operations	Guy line anchors. All guy line anchors shall be brightly marked pursuant to Rule 604.c (2)Q.
18	Final Reclamation	Well site cleared. Within 90-day subsequent to the time of plugging and abandonment of the entire site, superfluous debris and equipment shall be removed from the site.
19	Final Reclamation	Identification of plugged and abandoned wells. P&A'd wells shall be identified pursuant to 319.a.(5).

Total: 19 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
2107020	PROPOSED SPACING UNIT
2167800	MINERAL LEASE MAP
2167810	MINERAL LEASE MAP
400587268	FORM 2 SUBMITTED
400588731	OffsetWellEvaluations Data
400588742	DEVIATED DRILLING PLAN
400588750	EXCEPTION LOC REQUEST
400588752	WAIVERS
400592404	WELL LOCATION PLAT
400592408	DIRECTIONAL DATA
400598464	EXCEPTION LOC WAIVERS

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Oper. submitted PSU for 960 GWA wellbore spacing unit. Corrected dist. to nearest well. No LGD or public comments. Final Review--passed.	7/4/2014 1:39:24 PM
Permit	Corrected mineral lease description, acres in lease, distance to lease line, and mineral lease from State to Fee as per opr.	7/1/2014 11:39:13 AM
Permit	As per Opr attached Mineral Lease Map showing Synergy's Fee Leases.	6/12/2014 10:50:15 AM
Permit	Removed Exception Request for Property Line and unchecked the exception box. Attached corrected proposed spacing unit and corrected spacing unit acres, changing total acres from 960 to 240, as per opr. Corrected mineral owner to Fee, as per opr. Surface Restoration Bond on file with SLB; per Tim Kelly.	5/16/2014 7:48:24 AM
Permit	Distance to property line is more than 150'. No waiver is required and exception box should be unchecked. Emailed Tim Kelly at SLB for verification of Surface Restoration Bond. Proposed spacing unit is incorrect as it shows the lease not the individual proposed spacing unit. Opr notified.	5/15/2014 11:04:18 AM
Permit	Passed completeness	4/30/2014 11:42:15 AM
Permit	Return to draft per operator's request	4/25/2014 8:26:28 AM
Permit	Returned to draft. Minerals should be State, not Fee. Missing SUA. Distance to Building is greater than distance to Building Unit. Casing program is incomplete: stops at 7250'. Distance to property line is more than 150'. No waiver is required and exception box should be unchecked. First attachment labeled "Offset Well Evaluation" is list of water wells. Needs to be removed. Second attachment labeled "Offset Well Evaluation" is a drawing of the pad. Needs to be removed. Plats of the two sections must be on one attachment. Exception Location Request letter citing 350' setback is out of date. Needs to be removed. Corrected attachments labeled Directional Data to Deivated Drilling Plan and Multi-Well Plan. Corrected Exception Location Request attachment to Exception Location Waiver. Missing Exception Location Request for Rule 318A.a. Missing Proposed Spacing Unit attachment. Directional data not uploaded.	4/18/2014 2:12:04 PM

Total: 8 comment(s)