



## Re: RWF 43-25 Low TOC (045-21992)

1 message

**Krabacher - DNR, Jay** <jay.krabacher@state.co.us>  
To: "Porraz, Isac" <Isac.Porraz@wpxenergy.com>  
Cc: "Haddock, Reed" <Reed.Haddock@wpxenergy.com>

Tue, Jul 8, 2014 at 12:14 PM

Isac:

The CBL does show 'stringers' (& such) higher up -- as long as the bradenhead pressure (BHP) behaves ...

WPX has COGCC approval to conduct completion operations as planned. Of course, monitor the BHP and let us know if it increases more than 200 psi.

Regards,

Jay Krabacher

On Tue, Jul 8, 2014 at 9:54 AM, Porraz, Isac <Isac.Porraz@wpxenergy.com> wrote:

Mr. Krabacher,

The RWF 43-25 has a low production cement top. Please see the detailed information below:

Sec	Twn	Rng	Well	API	CBL TOC	Top of MVRD	Short*	Top of Gas	Approx. Planned Top Perf	Cmt over Perf	Bradenhead Press Before Completion
25	6S	94W	RWF 43-25	05-045-21992	5,322	5,107	-415	6,783	6,535	1,213	0
*Note: Assuming 200' above MVRD for cement coverage											

There is good coverage behind the zones of interest, TOG and planned top perf by 1,213ft. We have ratty cement bond just short of the MVRD, 415ft short, with respect to my interpretation. We'd like to proceed with completion on this well, which is scheduled for stimulation on Sunday July 13, 2014. I've attached the CBL for your review.

*Isac J. Porraz*

Petroleum Engineer



WPX ENERGY

1001 17th St, Suite 1200

Denver, CO 80202

(direct) 303-260-4521

(cell) 724-809-7647

isac.porraz@wpxenergy.com

Jay Krabacher

N W Area Engineer



**COLORADO**  
Oil & Gas Conservation  
Commission  
Department of Natural Resources

P 970.625.2497 x4

C 970.589.6180

796 Megan Ave., Suite 201, Rifle, CO 81650

[jay.krabacher@state.co.us](mailto:jay.krabacher@state.co.us) | [www.colorado.gov/cogcc](http://www.colorado.gov/cogcc)