

FORM
6
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400641794			
Date Received:			

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set. A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 100322 Contact Name: Erich Zwaagstra
 Name of Operator: NOBLE ENERGY INC Phone: (970) 371-7884
 Address: 1625 BROADWAY STE 2200 Fax: (970) 304-5099
 City: DENVER State: CO Zip: 80202 Email: ezwaagstra@nobleenergyinc.com

For "Intent" 24 hour notice required, Name: _____ Tel: _____
 Email: _____
COGCC contact: _____

API Number 05-123-13431-00 Well Number: E24-5
 Well Name: HERMAN
 Location: QtrQtr: SWNW Section: 24 Township: 6N Range: 65W Meridian: 6
 County: WELD Federal, Indian or State Lease Number: 67927
 Field Name: WATTENBERG Field Number: 90750

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.473601 Longitude: -104.618504
 GPS Data:
 Date of Measurement: 12/03/2009 PDOP Reading: 3.3 GPS Instrument Operator's Name: Paul Tappy
 Reason for Abandonment: Dry Production for Sub-economic Mechanical Problems
 Other _____
 Casing to be pulled: Yes No Estimated Depth: _____
 Fish in Hole: Yes No If yes, explain details below
 Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below
 Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
PARKMAN	3704	3705	08/07/1987	SQUEEZED	3704
CODELL	6995	7006	05/29/2014	B PLUG CEMENT TOP	6629
NIOBRARA	6679	6885	05/29/2014	B PLUG CEMENT TOP	6629

Total: 3 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	319	210	319	11	VISU
1ST	7+7/8	4+1/2	15.1	7,118	220	7,118	6,188	CBL
S.C. 1.1	7+7/8	4+1/2	15.1	3,725	125	3,725	3,600	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6629 with 2 sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
 CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
 CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 25 sks cmt from 3814 ft. to 3465 ft. Plug Type: CASING Plug Tagged:
 Set 100 sks cmt from 2521 ft. to 2321 ft. Plug Type: STUB PLUG Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 (Cast Iron Cement Retainer Depth)

Set 250 sacks half in. half out surface casing from 531 ft. to 0 ft. Plug Tagged:
 Set _____ sacks at surface
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No
 Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 2496 ft. of 4+1/2 inch casing Plugging Date: 06/02/2014
 *Wireline Contractor: Magna Wireline *Cementing Contractor: Magna Enegrgy Services
 Type of Cement and Additives Used: Class G Neat
 Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ross Snyder
 Title: Engineering Tech Date: _____ Email: rsnyder@nobleenergyinc.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400641796	OPERATIONS SUMMARY
400641797	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)