

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400643900

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: <u>47120</u>	4. Contact Name: <u>Katie Kistner</u>
2. Name of Operator: <u>KERR MCGEE OIL & GAS ONSHORE LP</u>	Phone: <u>(720) 9294317</u>
3. Address: <u>P O BOX 173779</u>	Fax: _____
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-</u>	

5. API Number <u>05-123-38827-00</u>	6. County: <u>WELD</u>
7. Well Name: <u>SCOTT</u>	Well Number: <u>26N-32HZ</u>
8. Location: QtrQtr: <u>SENE</u> Section: <u>5</u> Township: <u>2N</u> Range: <u>67W</u> Meridian: <u>6</u>	
Footage at surface: Distance: <u>2446</u> feet Direction: <u>FNL</u> Distance: <u>870</u> feet Direction: <u>FEL</u>	
As Drilled Latitude: <u>40.168451</u> As Drilled Longitude: <u>-104.907534</u>	

GPS Data:

Data of Measurement: 02/20/2014 PDOP Reading: 1.6 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 2259 feet. Direction: FNL Dist.: 276 feet. Direction: FEL

Sec: 5 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 510 feet. Direction: FNL Dist.: 2221 feet. Direction: FEL

Sec: 32 Twp: 2N Rng: 67W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 02/18/2014 13. Date TD: 05/22/2014 14. Date Casing Set or D&A: 05/24/2014

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 14570 TVD** 7156 17 Plug Back Total Depth MD 14511 TVD** 7156

18. Elevations GR 4874 KB 4890

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, GR, MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	1,017	383	0	1,017	VISU
1ST	8+3/4	7	26	0	7,533	757	400	7,533	CBL
1ST LINER	6+1/8	4+1/2	11.6	6569	14,560	420	6,575	14,560	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	7,172		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,245		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

COA for Openhole log has been removed per Sundry-(Scott 26N-32HZ, doc # 400570762)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Katie Kistner

Title: Regulatory Analyst

Date: _____

Email: katie.kistner@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400643909	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400643910	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400643906	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400643907	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400643908	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400644297	LAS-Measurement/Logging While Drilling	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400644298	PDF-Measurement/Logging While Drilling	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)