

State Pronghorn 11-16
 721 FNL828 FWL NWNW 16 5N 61W 6th PM
 Lat 40.40642 Long -104.22069 (from footages)
 Weld County, Colorado
 API #05-123-24330

Spud date 12/5/2006

4646 KB
 4636 GL

8.625", 24#/ft Wt, Grade, 362', 12.25" hole
 Cemented to surface

Water N/A -- Outcrop
 (Within 1 mile radius)

Parkman 3227 '

As found in well:
 State Pronghorn 11-16

TOC 5400 '

Niobrara 6007 '

Fort Hayes 6238 '

Codell 6275 '

D Sand 6673 '

J Sand 6740 '

Completion Summary

Completed the Niobrara Jan 2007
 Completed with 60 holes (6012 - 6178)

Drilled to J-sand, plugged back above D Sand

4 1/2", 10.5#/ft Wt, Grade, 6469, 7 7/8" hole
 Cemented with 377 sxs

PBTD 6448 ft
 TD 6867 ft 12/11/2006

Updated 7/15/2014 jad