

NGL Water Solutions DJ, LLC

NGL SWD C-11

To be Determined

Formation	Tops	Btm	Porosity	TDS	Frac Gradient	Permeability
Lyons	7791	8071	16%	19,383		
Lower Satanka	8071	8131	2%	19,393		
Wolfcamp	8131	8225	0%	3,814		
Amazon	8225	8280	23%	4,179		
Council Grove	8280	8420	14%	4,179		
Admire	8420	8464	10%	11,441		
Virgil	8464	8668	16%	11,441		
Missouri	8668	8928	12%	11,441		
Fountain (Desmoinesian)	8953	9330	2%	14,585		
Morrow	9450	TD	2%	14,585		

*Depths are based on the Colorado National Bank well (05-123-05582)

**TDS is estimated from the SWD C7A (05-123-32207)

***Porosity is estimated for net pay only, based on Bonanza Creek 34-24 Antelope (05-123-38290) and Tennessee Gas 1 Bolin (05-123-05228) and Barnes 3 Rosener (05-087-08081)