

US ROCKIES REGION

Anadarko Daily Summary Report

Well: ACORD GILBERT GU #1

Project: COLORADO-WELD-NAD83-UTM13

Site: ACORD GILBERT GU #1

Rig Name No: LEED 724/724

Event: ABANDONMENT

Start Date: 7/1/2014

End Date:

Spud Date: 6/23/1975

Active Datum: RKB @4,800.99usft (above Mean Sea Level)

UWI: 0/3/N/67/W/29/0/SESW/6/PM/S/990.00/W/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	06/25/2014		MIRU CORE-TECH SL FISHED TOOLS @7620' TAG FILL @ 7671' & RUN PRESSURE BOMB.
2	07/01/2014		MIRU Leed 724 TP:700, CP:700, SP:0. Blew down well & controlled it. NDWH NUBOP TOO H 254 jts MIRU Pioneer WL RIH G-ring & J-basket to 7643' set 4.5 CIBP @ 7580' PT CIBP to 1000/15 mins held good, spot 2 sks CMT on plug RDWL SWI SDFN
3	07/02/2014		RU Pioneer WL run CBL from 7580' up to surface found good CMT from 7580' up to 6940' RIH shot SQ holes @ 6940' & 6540' set CICR @ 6580' RD WL RU H-S tester tested tbg in to 6580' RU Baker pumped 20 bbls SMS & 130 sks 50/50 poz G cmt 13.5ppg, 1.71 cf/sk
4	07/03/2014		MIRU Pioneer WL RIH shot SQ holes @ 4480' & 3880' set CICR @ 3910' TIH w/stinger to 3910' waited for cementers RU Baker pumped 20 bbls SMS & 450 sks G CMT 15.8ppg, 1.15cf/sk RD Baker TOO H SWI SDFN
5	07/07/2014		RU Pioneer WL RIH jet cutter cut csg @ 930' RDWL circulated gas out NDBOP & WH unlanded csg spool&NUBOP TOO H LD csg (rig broke down) TIH 2 3/8 tbg to 1030 RU Baker pumped 550 sks type III CMT 14.8 ppg, 1.34 cf/sk RD Baker TOO H SWI SDFN
6	07/08/2014		TIH tag TOC @ 90' LD tbg NDBOP & spool MIRU Pioneer WL RIH set Centennial's 8 5/8 CIBP @ 80' RDWL NUBOP PT CIBP to 1000/15 mins held good. RDMO Leed 724.
7	07/18/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 70'. Filled casing stub with 31 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled.