

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: AMEN 1			
Project:COLORADO-WELD-NAD83-UTM13		Site:AMEN 1	Rig Name No:KEY 104/104
Event: ABANDONMENT		Start Date: 6/27/2014	End Date: Spud Date: 12/27/1983
Active Datum: RKB @4,930.99usft (above Mean Sea Level)		UWI: 0/5/N/67/W/20/0/NWNW/6/0/0/0/0/0/0	
Report No	Report Date	MD (usft)	24 Hr Summary
1	06/27/2014		MIRU Key 104.
2	06/30/2014		CREW TRAVEL TO LOC. ND WH, NU BOPS. PULL 2 STANDS OUT TBG PLUG. RU WIRELINE TO SHOT A HOLE ON TBG.CANT PASS 500'.RD WIRELINE,PULL 10 STRANDS. RU WIRELINE. RUN IH HOLE,CANT PASS 4700'. PUMP WATER DOWN TBG. BRAKE CIRCULATION. RD WIRELINE.PUMP 80 BBLS TOO. H.
3	07/01/2014		RU WIRELINE, RIH, COULDN'T GET PAST 6400', RD WIRELINE, TIH W/ 3-7/8" BIT, TAG @ 6400', CLEAN OUT TO 7000', TOO. H, SWI, SDFN
4	07/02/2014		RU WIRELINE, FINISH GYRO'ING WELL FROM 6400'-6930', SET 4-1/2" CIBP @ 6775', PT CIBP TO 1000PSI - DIDN'T HOLD, HELD @ 550PSI, LOG WELL FROM 6775'-SURFACE, RD WIRELINE, TIH, EOT @ 6760', PUMP 25SX OF 15.8# CLASS G CEMENT, TOO. H, LD TBG, SWI, SDFN
5	07/03/2014		RU WIRELINE, RIH, TAG TOC @ 5420', SHOOT HOLES @ 4380'-4381' & 3760'-3761', RD WIRELINE, TIH, SET 4-1/2" CIBP @ 3811', RU CEMENTERS, PUMP 310SX OF 15.8# CLASS G CEMENT, TOO. H, LD TBG, SWI, SDFN
6	07/07/2014		RD FLOOR & TONGS, RU WIRELINE, RIH, TAG TOC @ 2925', CUT CSG @ 830', RD WIRELINE, CIRCULATE WELL, ND BOP, UNLAND CSG, NU BOP, RU FLOOR & TONGS, TOO. H, LD CSG, TIH, EOT @ 930', RU CEMENTERS, PUMP 350SX OF 14.8# TYPE 3 CEMENT, TOO. H, LD TBG, SWI, SDFN
7	07/08/2014		ND BOP & SPOOL, RU WIRELINE, RIH, TAG TOC @ 150', SET 8-5/8" CIBP @ 80', RD WIRELINE, TEST CIBP TO 1000PSI - HELD, RDMO KEY 104
8	07/21/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 71'. Filled casing stub with 33 bags 5000# cement. Capped casing with metal plate containing well info. Backfilled.

COMMENTS:

07/01/14 - TAG @ 6400', LD 22JTS TO TRIP PIPE OUT OF DERRICK, TAGGED UP @ 6370', MIGHT HAVE HOLE IN CSG, CLEAN OUT TO 7000', CIRCULATED OUT DRILLING MUD

07/03/14 - GOOD RETURNS THROUGHOUT CEMENT JOB

07/07/14 - COLLAR @ 820', CUT CSG @ 830', ROLL HOLE CLEAN @ 120' AFTER CEMENT JOB

07/08/14 - PRESSURE TESTED CIBP TO 1000PSI, BLEW APART AT 8-5/8" COLLAR BELOW WELLHEAD, BY FOLLOWING PROCEDURE, NOBODY WAS INJURED