

**FORM**  
**5**  
Rev  
02/08

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
400648603

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 8960 4. Contact Name: Bryan Brown  
 2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-6100  
 3. Address: 410 17TH STREET SUITE #1400 Fax: (720) 279-2331  
 City: DENVER State: CO Zip: 80202

5. API Number 05-123-39024-00 6. County: WELD  
 7. Well Name: Wetco Farms Well Number: A-4-9MRLC  
 8. Location: QtrQtr: NWNW Section: 4 Township: 4N Range: 63W Meridian: 6  
 Footage at surface: Distance: 274 feet Direction: FNL Distance: 170 feet Direction: FWL  
 As Drilled Latitude: 40.347940 As Drilled Longitude: -104.451680

GPS Data:  
 Date of Measurement: 05/29/2014 PDOP Reading: 1.8 GPS Instrument Operator's Name: Wyatt Hall

\*\* If directional footage at Top of Prod. Zone Dist.: 725 feet. Direction: FNL Dist.: 23 feet. Direction: FWL

Sec: 4 Twp: 4n Rng: 63w

\*\* If directional footage at Bottom Hole Dist.: 2141 feet. Direction: FNL Dist.: 24 feet. Direction: FWL

Sec: 9 Twp: 4n Rng: 63w

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 04/07/2014 13. Date TD: 04/14/2014 14. Date Casing Set or D&A: 04/15/2014

15. Well Classification:

Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 13795 TVD\*\* 6523 17 Plug Back Total Depth MD 13795 TVD\*\* 6523

18. Elevations GR 4569 KB 4586

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

mud, cbl, resistivity

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	785	250	0	785	CALC
1ST	8+3/4	7	26	0	6,906	718	320	6,906	CBL
1ST LINER	6+1/8	4+1/2	11.6	6768	13,847				

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,147		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,274		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

open hole logs on offset well Wetco Farms 11-4 05-123-22501; no sussex or shannon identified.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Bryan Brown

Title: Drilling Engineer Date: \_\_\_\_\_ Email: bbrown@bonanzacrck.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400648855	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400648853	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400648643	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400648649	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400648818	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400648851	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)