

# Jumbo #3

As Plugged 10/24/13

Red Mesa Field

689' FNL & 2321' FWL, Section 27, T-33-N, R-12-W, La Plata County, CO

Lat: N 37.08064 / Long: W -108.13869 / API #05-067- 06786

Today's Date: **2/4/14**

Spud: 12/10/84

Completed: 4/25/85

Elevation: 6538' GI

15" hole

8.5" hole

6.25" hole

TD 600'

TOC @ surface (Calc 75%)

**Surface Plug/ P&A  
marker**  
Class B cement, 24 sxs

**Plug #2: 100' – 0'**  
Class B cement, 24 sxs

**Plug #1: 360' – 157'**  
Class B cement, 40 sxs

7" 20# Casing set @ 300'  
Cmt with 150 sxs,

