

EnCana Oil & Gas (USA) Inc.

Well : JILLSON GAS UNIT #1
Field : Wattenberg
County : Weld County **State** : Colorado
Surface : Lat: 40.1196338 Long: -104.9923962
: 990 FSL, 1650 FWL Sec 22 T2N R68W
API # : 05-123-09758
Grd Elev : 4966' GR **KB Elevation:** 4977' KB

Log Tops:

Fox Hills Base 300'
Sussex 4382'
Niobrara 7298'
Codell 7579'
J Sand 8007'

Surface Casing

8-5/8" Surface Casing set
@ 213', cmt'd w/ 200 sx

TOC @ Unknown

Production Casing

4-1/2" production casing set @ 8144'.
Cmt w/ 225 sx

Production Tubing

Unknown

Sleeve @ 642' w/ 1000 gal An-Gel

J Sand Perfs

8020-8038'
Frac'd with 177,600 gal Versagel and
40,600# 100 mesh, 201,600# 20/40 sand
and 110,600# 10/20 SS(10/20/1994)

TD 8140'

Well History:

Spud 11/10/79
TD 11/18/79

Drawn by:
Scott Reed

Date:
07/23/2014