

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400638614

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96155
2. Name of Operator: WHITING OIL AND GAS CORPORATION
3. Address: 1700 BROADWAY STE 2300
City: DENVER State: CO Zip: 80290
4. Contact Name: Pauleen Tobin
Phone: (303) 837-1661
Fax: (303) 495-6780
Email: pollyt@whiting.com

5. API Number 05-123-37765-00
6. County: WELD
7. Well Name: Razor
Well Number: 21B-2811A
8. Location: QtrQtr: NWNE Section: 21 Township: 10N Range: 58W Meridian: 6
9. Field Name: DJ HORIZONTAL NIOBRARA Field Code: 16950

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 01/27/2014 End Date: 02/08/2014 Date of First Production this formation: 03/15/2014

Perforations Top: 6245 Bottom: 12727 No. Holes: 1440 Hole size: 3/8

Provide a brief summary of the formation treatment: Open Hole: ☐

Cemented Liner, 40 stage YF825LpH, 114552# 40/70, 5294950# 20/40, 648 bbls 15% HCl, 119634 bbls slickwater. See attached wellbore diagram for details.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 119634 Max pressure during treatment (psi): 8003

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.33

Type of gas used in treatment: Min frac gradient (psi/ft): 0.80

Total acid used in treatment (bbl): 648 Number of staged intervals: 40

Recycled water used in treatment (bbl): 0 Flowback volume recovered (bbl): 43652

Fresh water used in treatment (bbl): 114460 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 5409502 Rule 805 green completion techniques were utilized: ☐

Reason why green completion not utilized: PIPELINE

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/19/2014 Hours: 24 Bbl oil: 277 Mcf Gas: 239 Bbl H2O: 489

Calculated 24 hour rate: Bbl oil: 277 Mcf Gas: 239 Bbl H2O: 489 GOR: 863

Test Method: Separator Casing PSI: 660 Tubing PSI: 240 Choke Size: 64/64

Gas Disposition: FLARED Gas Type: DRY Btu Gas: 1281 API Gravity Oil: 36

Tubing Size: 2 + 7/8 Tubing Setting Depth: 5859 Tbg setting date: 03/14/2014 Packer Depth: 5859

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Pauleen Tobin

Title: Engineer Tech

Date: _____

Email pollyt@whiting.com

:

Attachment Check List

Att Doc Num

Name

400638628

WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)