



Continental Industries Field Services, LLC
 2411 N. Oil Drive
 P.O. Box 656
 Casper, WY 82602

307-473-1581 Phone
 307-234-1035 Fax

www.wellplugging.com

DAILY WORK TICKET

Company: Chesapeake Energy
 Address: 5880 Enterprise # 600
Casper WY, 82609
 AFE # 802882 Property # 733242

Date: 6/19/2014 Rig: 4
 Lease: Wildcat
 Well: State 2-16-1
 County: Weld

PLUGGING / WORK DETAIL:

Conduct safety meeting, TIH open ended and tagged TOC @ 741', consulted Chesapeake rep, L/D tubing. RDSU, ND BOP. Moved equipment over to the Brent well, spotted anchors, and containments while waiting on cement. Dig out monitored LEL, H2S, CO2, all were 0's, oxygen was normal 21%, fill out HW permit, cut off wellhead 5'bgl, RU cementers, top off casings as follows, 25sxs cement in production casing, 20sxs cement in the annulus, weld on dry hole plate with legals, backfill cellar. SDFN.

ITEM	HOURS OR UNITS	PRICE PER HOUR	TOTAL
------	----------------	----------------	-------

BID PRICE	1		\$
-----------	---	--	----

ADDT'L TIME & MATR'L ITEMS:			
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
SUB TOTAL:			\$
SALES TAX:			\$
TOTAL:			\$

EMPLOYEE'S NAME	JOB	HOURS
-----------------	-----	-------

Ryan LeMay	Supervisor	
Brett Devoe	Operator	
Nick Klassen	Derrick	
Rick McComsey	Floor	
Ryan LeMay	CMTR	
Todd VanCoillie	BULK	
B.Velasquez	Co. Rep	

CEMENT DETAIL

Cement pumped was class G Neat with slurry weight of 15.8 ppg, 1.15 cu-ft/sk yield. Mix water was 4.96 gal/sk. Compressive strength 24 hrs/4000 psi

PREPARED BY: RL