

FORM 5A

Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400566481

Date Received: 03/05/2014

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: GINA RANDOLPH
Phone: (303) 260-4509
Fax: (303) 629-8268
Email: GINA.RANDOLPH@WPXENERGY.COM

5. API Number 05-045-21771-00
6. County: GARFIELD
7. Well Name: Federal
Well Number: RU 12-5
8. Location: QtrQtr: LOT2 Section: 5 Township: 7S Range: 93W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 01/24/2014 End Date: 01/27/2014 Date of First Production this formation: 01/24/2014

Perforations Top: 7830 Bottom: 9939 No. Holes: 158 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: []

1321 Gals 7 1/2% HCL; 927100# 40/70 Sand: 25824 Bbls Slickwater (Summary)

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 25856 Max pressure during treatment (psi): 6559
Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43
Type of gas used in treatment: Min frac gradient (psi/ft): 0.66
Total acid used in treatment (bbl): 31 Number of staged intervals: 7
Recycled water used in treatment (bbl): 25824 Flowback volume recovered (bbl): 8614
Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE
Total proppant used (lbs): 927100 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 02/12/2014 Hours: 24 Bbl oil: 0 Mcf Gas: 584 Bbl H2O: 0
Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 584 Bbl H2O: 0 GOR: 0
Test Method: FLOWING Casing PSI: 2350 Tubing PSI: 670 Choke Size: 9/64
Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1090 API Gravity Oil: 0
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

All flowback water entries are total estimates based on commingled volumes.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: GINA RANDOLPH
Title: PERMIT TECH II Date: 3/5/2014 Email GINA.RANDOLPH@WPXENERGY.COM
:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400566481	FORM 5A SUBMITTED
400566511	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Passes Permitting.	7/28/2014 7:03:40 AM

Total: 1 comment(s)