

Federal #7-27
2250' FNL & 2240' FEL SW NE Sec 27-T9N-R78W, 6th P.M.
Jackson County, Colorado
API # 05-057-06306

P&A Procedure

Well Status: PR SI

1. MIRU service rig, pump and tank
2. RIH w/ 2 3/8" work string to 620', circulate hole clean
3. MIRU cementers, pump 50 sx Glass G, 1.15 yield, 15.8 ppg cement. POOH keeping EOT in cement.
4. Place 50 ft of cement in 4 1/2 x 7 annulus, 5 sx.
5. RD and monitor cement level in 4 1/2" casing and annulus.
6. Top off 4 1/2" and 7" as needed
7. Cut casing 4' below surface and weld on plate with weep hole.
8. Plate to contain following info.

Bonanza Creek Energy Company, Inc
Federal 7-27
API No. 05-057-06306
SWNE 27 9N 78W