

FORM  
2A

Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400635271

Date Received:

Oil and Gas Location Assessment

☐ New Location ☐ Refile ☒ Amend Existing Location Location#: 436998

Submit signed original form. This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

**436998**

Expiration Date:

☐ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # \_\_\_\_\_
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 69175  
Name: PDC ENERGY INC  
Address: 1775 SHERMAN STREET - STE 3000  
City: DENVER State: CO Zip: 80203

Contact Information

Name: Julie Webb  
Phone: (303) 831-3933  
Fax: ( )  
email: julie.webb@pdce.com

RECLAMATION FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID: 20090078 ☐ Gas Facility Surety ID: \_\_\_\_\_  
☐ Waste Management Surety ID: \_\_\_\_\_

LOCATION IDENTIFICATION

Name: Becker Ranch Number: 5MR-TB Pad  
County: WELD  
QuarterQuarter: NWNE Section: 5 Township: 3N Range: 64W Meridian: 6 Ground Elevation: 4782  
Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.  
Footage at surface: 536 feet FNL from North or South section line  
1567 feet FEL from East or West section line  
Latitude: 40.260280 Longitude: -104.570980  
PDOP Reading: 1.8 Date of Measurement: 07/18/2013  
Instrument Operator's Name: Adam Kelly

## RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

**This proposed Oil and Gas Location is:**

**LOCATION ID #**

**FORM 2A DOC #**

Production Facilities Location serves Well(s)

436185

## FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	Oil Tanks	18	Condensate Tanks	Water Tanks	6	Buried Produced Water Vaults	3
Drilling Pits	Production Pits		Special Purpose Pits	Multi-Well Pits		Temporary Large Volume Above Ground Tanks	8
Pump Jacks	Separators	6	Injection Pumps	Cavity Pumps			
Gas or Diesel Motors	Electric Motors		Electric Generators	Fuel Tanks		Gas Compressors	
Dehydrator Units	Vapor Recovery Unit	2	VOC Combustor	3	Flare	LACT Unit	
						Pigging Station	

## OTHER FACILITIES

**Other Facility Type**

**Number**

Meter Run

1

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

Each well will have a flow line, oil production line, water production line and a backpressure line, each battery will have a gas sales line. Oil production line and flow lines are 3 inch steel SCH 80FB PE DRL. Water production line and low pressure gas vent lines are 2 inch SDR7 poly. Gas sales lines installed and maintained by Gas Purchaser, normally 6 inch steel .256 FBE

## CONSTRUCTION

Date planned to commence construction: 08/25/2014

Size of disturbed area during construction in acres: 10.20

Estimated date that interim reclamation will begin: 02/25/2015

Size of location after interim reclamation in acres: 1.30

Estimated post-construction ground elevation: 4782

## DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes

Is H<sub>2</sub>S anticipated? No

Will salt sections be encountered during drilling: No

Will salt based mud (>15,000 ppm Cl) be used? No

Will oil based drilling fluids be used? No

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal:

Drilling Fluids Disposal Method:

Cutting Disposal:

Cuttings Disposal Method:

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable:

## SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: Becker Ranch, LLC

Phone: \_\_\_\_\_

Address: 25517 WCR 36

Fax: \_\_\_\_\_

Address: \_\_\_\_\_

Email: \_\_\_\_\_

City: LaSalle State: CO Zip: 80645

Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☒ is the mineral owner

☒ is committed to an oil and Gas Lease

☐ has signed the Oil and Gas Lease

☐ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: Yes

The right to construct this Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

Date of Rule 306 surface owner consultation 06/04/2014

## CURRENT AND FUTURE LAND USE

### Current Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): \_\_\_\_\_

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

### Future Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): \_\_\_\_\_

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1092 Feet  
Building Unit: 1845 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 693 Feet  
Above Ground Utility: 1150 Feet  
Railroad: 5280 Feet  
Property Line: 453 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 72: Vona Loamy Sand

NRCS Map Unit Name: \_\_\_\_\_

NRCS Map Unit Name: \_\_\_\_\_

## PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☒ No ☐

Plant species from: ☒ NRCS or, ☐ field observation Date of observation: \_\_\_\_\_

List individual species: \_\_\_\_\_

Check all plant communities that exist in the disturbed area.

- ☒ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)  
☒ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)  
☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)  
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)  
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)  
☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)  
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)  
☐ Alpine (above timberline)  
☐ Other (describe): \_\_\_\_\_

## WATER RESOURCES

Is this a sensitive area: ☒ No ☐ Yes

Distance to nearest

downgradient surface water feature: 5280 Feet

water well: 1358 Feet

Estimated depth to ground water at Oil and Gas Location 25 Feet

Basis for depth to groundwater and sensitive area determination:

Sensitive area determination: ground water is greater than 20'. Depth to ground water determination: Surface owner experience

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer No zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: \_\_\_\_\_

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

The MLVT will be onsite for 180 days and contains 53,000 bbls per tank. MLVT manufacturers currently used by PDC are Industrial Systems Inc. (ISI) and PCI Manufacturing. Distance from MLVT to Property line 695'.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: \_\_\_\_\_ Date: \_\_\_\_\_ Email: julie.webb@pdce.com

Print Name: Julie Webb Title: Regulatory Analyst

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

### **Conditions Of Approval**

**All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.**

## Best Management Practices

No	BMP/COA Type	Description
1	Planning	<p>1) PDC determines MLVT locations based on size of location, nearby surface waters, site visibility, surrounding land use, property lines, onsite traffic, site security, tearaway tank fill connections, topography (high, low, slope, direction), nearby building units, roads, access points, and surface owner requests.</p> <p>2) Signs shall be posted on each MLVT to indicate that the contents are fresh water and that no E&amp;P waste fluids are allowed. Location and additional signage shall conform to Rule 210.</p> <p>3) MLVTs will be operated with a minimum of 1 foot freeboard at all times.</p> <p>4) Access to the tanks shall be limited to operational personnel.</p> <p>5) Construction and installation of the tank structure, liner and sub-grade shall meet or exceed the manufacturer specifications. PDC follows manufacturer's Standard Operating Procedures (SOPs) and will provide these SOPs upon request to the COGCC.</p> <p>6) PDC will conduct daily, visual inspections of the exterior wall and general area for any integrity deficiencies before, during, and after filling the MLVTs. PDC uses Construction Sign-Off, Site Preparation Sign-Off, Completion Sign-Off, Pre-Fill, and Site Visit checklists to maintain a written record of inspections. However, when the fluid level in the MLVTs is less than two (2) feet and there is no activity going on (i.e. during holidays or a small break between completions), only intermittent inspections will be conducted. Two feet is the safe volume of fluid level that is needed to hold the liner down and keep the MLVT stable.</p> <p>7) Each location where MLVT's are used will have its own set of unique site-specific characteristics and associated risks (e.g., rural vs. urban setting, grade of the location, etc.) to be considered in a worst case scenario. These characteristics must be identified and addressed prior to the MLVT construction phase and should be documented in the MLVT construction checklist. Ensuring the safety of our employees, contractors, and the public are a top priority. This can be addressed with the implementation of MLVT pre-construction risk assessment measures to address safety concerns, and minimize environmental impacts and property damage in the unlikely event of a MLVT release.</p> <p>8) In the event of a catastrophic MLVT failure, the Operator shall notify the COGCC as soon as practicable but not more than 24 hours after discovery, submit a Form 22-Accident Report within 10 days after discovery, conduct a "root cause analysis", and provide same to COGCC on a Form 4-Sundry Notice within 30 days of the failure.</p>
2	Storm Water/Erosion Control	<p>Stormwater Management Plan contains required elements associated with PDC's construction activities for Areas 1, 2, 3, and 5, as defined in the CDPS General Permit for Stormwater Discharges Associated with Construction Activity, Authorization to Discharge Under the Colorado Discharge Permit System (Permit No. COR-030000, reissued and effective July 1, 2007).BMPs for sediment and erosion control will be accomplished through a combination of construction techniques, vegetation and revegetation, administrative controls, and structural features.</p>
3	Material Handling and Spill Prevention	<p>To prevent adverse impacts to shallow groundwater, buried produced water vault shall be installed above an impermeable synthetic or geosynthetic liner system which shall be tied back into the surface liner.</p>

Total: 3 comment(s)

### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400635290	ACCESS ROAD MAP
400635293	HYDROLOGY MAP
400635295	LOCATION DRAWING
400635296	LOCATION PICTURES
400635297	OTHER
400650648	WASTE MANAGEMENT PLAN
400650649	NRCS MAP UNIT DESC
400651249	OTHER

Total Attach: 8 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)