

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

268495

TICKET NUMBER 46960

LOCATION Oakley To

FOREMAN *[Signature]*

FIELD TICKET & TREATMENT REPORT

miles Co.

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5/28/14	9160	Ma State #10	24	10	56	Lincoln
CUSTOMER <u>Wierking Fullerton</u>						
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			731	Jermey		
			460	Steven		
CITY						
STATE		ZIP CODE				

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>330</u>	CASING SIZE & WEIGHT <u>8 5/8 24'</u>
CASING DEPTH <u>324.37</u>	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT <u>14.8</u>	SLURRY VOL <u>1.86</u>	WATER gal/sk	CEMENT LEFT in CASING
DISPLACEMENT <u>18.75</u>	DISPLACEMENT PSI	MIX PSI	RATE

REMARKS: Softly meeting Rig on Schaefer Big Run casing Break Circulate with Rig Pump Hook up to Pump Truck mix 175 SKs Cem 3%CC 2%Gel Wash up Pump + Lines Displace with 18.75 bbl water Shut in Cement Did Circulate

Approx 10 bbls to Pipe

Thanks Daven & Croc

[illegible]

Ravin 3737

AUTHORIZATION Approved

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

268885

TICKET NUMBER 46992

LOCATION Oakley, KS

FOREMAN Dane Pätzloff

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-16-14	9160	M2-State # 10	24	10	56	Lincoln
CUSTOMER <u>Wiepking</u>			CITY			
MAILING ADDRESS			STATE			
CITY			ZIP CODE			
Limon RD 26 Gas Plant RD.			CITY			
TRUCK #			DRIVER			
456			mike			
530			Steve			

JOB TYPE Production HOLE SIZE 7 7/8 HOLE DEPTH 8000 CASING SIZE & WEIGHT 5 1/2 17#
CASING DEPTH 7995 DRILL PIPE 4.5 TUBING NA OTHER PC at 4772
SLURRY WEIGHT 14.5 SLURRY VOL 1.53 WATER gal/sk 7.3 CEMENT LEFT in CASING 25
DISPLACEMENT 124.90/190.4 DISPLACEMENT PSI 100 MIX PSI 200 RATE mix at 6.8812 per min / displace 666

REMARKS: Setting meeting. Rig up. Run float equipment. Turbos on 2, 3, 4, 9, 12, 15, 18, 19, 20, 21, 23, 23. Baskets on 4 and 10' below pr on joint 76. Cents on 75 and 77. 100 joints down circulate for 30 min. On bottom circulate till vis is at 45. Pump 5 bbls of water ahead. mix mudflush pump 5 behind. Plug bathole and mousehole with 10 SKs each. mix 240 SKs of class # cement 2% Bentonite. 5# Kol seal 10% salt .25 flu seal. wash pump & lines. Release plug. Displace 184 bbls of water. Final lift pressure 1200 psi. Plug landed at 1900 psi. 76.29 slurry BRls to mix. Pipe string OFF bottom 7 feet

Thanks Dane + crew.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401c	1	PUMP CHARGE	3175.00	3175.00
5406	100	MILEAGE	5.25	525.00
5407A	14.57	Ton Mileage Delivery	1.75	2550.00
1115A	310 SKs	Class # Cement	16.175	5192.50
1110A	1550	Kol seal	.56	868.00
1107	77	Flu seal	2.97	228.69
1118B	582	Bentonite	.97	157.14
1111	2000 1342	Salt	.50	671.00
4104	3	5 1/2 Basket	290.00	580.00
4136	14	5 1/2 Turbolizers	75.75	1060.50
4159	1	5 1/2 AFE Float shoe	433.75	433.75
4454	1	5 1/2 Latchdown Plug Assembly	567.00	567.00
1144G	500 gal	Mudflush	1.00	500.00
4285	1	5 1/2 Port Collar	2178.75	2178.75
			Sub	18687.33
			10%a	1868.73
			Total	16818.60
			SALES TAX	850.30
			ESTIMATED TOTAL	17674.90

Ravin 3737

AUTHORIZATION Darryl Smith TITLE CO-REP DATE 6/16/14

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

268980

TICKET NUMBER 46933

LOCATION Oglethorpe, MS

FOREMAN Miles Shaw

FIELD TICKET & TREATMENT REPORT

CEMENT

60

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
10-20-14	9160	Mo State #10		24	10S	56W	Lincoln
CUSTOMER Wrephing Fullerton				TRUCK #			
MAILING ADDRESS				DRIVER			
CITY				TRUCK #			
STATE				DRIVER			
ZIP CODE							

JOB TYPE <u>Portacoker</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2" 12#</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8"</u>	OTHER <u>PC 09750'</u>
SLURRY WEIGHT <u>12.11</u>	SLURRY VOL <u>1.9</u>	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>26 1/2</u>	DISPLACEMENT PSI <u>520</u>	MIX PSI <u>1500</u>	RATE _____

REMARKS: Safety meeting and rig up on coded well serving Test casing to 1500ps.
Establish Circulation mix 250 SWS 40/40oz 8% gel 28 calcium %
Flueal displace down with 26 1/2 bbls water Shut test to 1500ps.
Run in 6 SWS Reverse clean with 50 bbls water test test to 1500ps.
Rise down

Thanks Miles & Co.

[illegible]

Ravin 3737

AUTHORIZATION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.