

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400589395

Date Received:

05/12/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refiling ☐

ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒

Sidetrack ☐

Well Name: FEDERAL

Well Number: RGU 44-23-198

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

Contact Name: ANGELA NEIFERT-KRAISER Phone: (303)606-4398 Fax: (303)629-8268

Email: ANGELA.NEIFERT-KRAISER@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 23 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.944726 Longitude: -108.353615

Footage at Surface: 1048 feet FNL/FSL FSL 623 feet FEL/FWL FEL

Field Name: SULPHUR CREEK Field Number: 80090

Ground Elevation: 6570 County: RIO BLANCO

GPS Data:

Date of Measurement: 03/19/2014 PDOP Reading: 2.8 Instrument Operator's Name: J KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

1209 FSL 632 FEL 1209 FSL 632 FEL
Sec: 23 Twp: 1S Rng: 98W Sec: 23 Twp: 1S Rng: 98W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1S-R98W 6TH P.M.
SEC. 23: LOTS 1-16
SEC. 26: LOTS 2-16

Total Acres in Described Lease: 1205 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC060732

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 632 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 3458 Feet
Building Unit: 3458 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 3532 Feet
Above Ground Utility: 957 Feet
Railroad: 5280 Feet
Property Line: 5280 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 344 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 4129 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): RYAN GULCH UNIT Unit Number: COC68239X

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
WILLIAMS FORK	WMFK			

DRILLING PROGRAM

Proposed Total Measured Depth: 12645 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 344 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	30	80	0
SURF	14+3/4	9+5/8	36	0	3894	1415	3894	0
1ST	8+3/4	4+1/2	11.6	0	12645	1304	12645	7580

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 433287

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: ANGELA NEIFERT-KRAISER

Title: REGULATORY SPECIALIST Date: 5/12/2014 Email: ANGELA.NEIFERT-

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 7/30/2014

Expiration Date: 07/29/2016

API NUMBER

05 103 12136 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. SEE ATTACHED NOTICE. (2) PROVIDE CEMENT COVERAGE FROM THE PRODUCTION CASING (4+1/2" FIRST STRING) SHOE TO A MINIMUM OF 200 FEET ABOVE ALL MESAVERDE GROUP (AND OHIO CREEK, IF PRESENT) OIL, GAS, AND WATER-BEARING SANDSTONE AND COALBED FORMATIONS. VERIFY PRODUCTION CASING CEMENT COVERAGE WITH A CEMENT BOND LOG.

Best Management Practices

No	BMP/COA Type	Description
1	Planning	<ul style="list-style-type: none"> * Share/consolidate corridors for pipeline ROWs to the maximum extent possible. * Locate roads outside of drainages where possible and outside of riparian habitat. * Minimize the number, length, and footprint of oil and gas development roads * Use existing roads where possible * Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors * Combine and share roads to minimize habitat fragmentation * Maximize the use of directional drilling to minimize habitat loss/fragmentation * Maximize use of remote completion/frac operations to minimize traffic * Maximize use of remote telemetry for well monitoring to minimize traffic
2	Construction	<ul style="list-style-type: none"> * Structures for perennial or intermittent stream channel crossings should be constructed using appropriately sized bridges or culverts * Design road crossings of streams at right angles to all riparian corridors and streams to minimize the area of disturbance to the extent possible. Construct retention basins and ponds that benefit wildlife
3	Drilling/Completion Operations	<ul style="list-style-type: none"> * Use centralized hydraulic fracturing operations. * Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures). * Conduct well completions with drilling operations to limit the number of rig moves and traffic.
4	Interim Reclamation	<ul style="list-style-type: none"> * Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation requirements * Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife * WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeded and reclamation of disturbed areas. * Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings. * Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400589395	FORM 2 SUBMITTED
400606917	DIRECTIONAL DATA
400606919	DEVIATED DRILLING PLAN
400606921	FED. DRILLING PERMIT
400606943	WELL LOCATION PLAT
400606944	ACCESS ROAD MAP

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed. No LGD comments.	7/30/2014 8:53:37 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 3001 FEET DEEP. Evaluated existing offset wells within 1,500 feet of this wellbore. No mitigation required.	5/16/2014 2:30:02 PM
Permit	Passed completeness	5/13/2014 4:03:11 PM

Total: 3 comment(s)