



DRILLING COMPANY, INC.

WICHITA, KANSAS

Current Wellbore Configuration

Date:	8/1/2014
Well Name:	Schluntz #1
Location:	SW NW 30-13-43
County:	Cheyenne
State:	Colorado
API:	05-017-06462
KB:	4179'
GL:	4167'
Spud Date:	7/18/1984

13-3/8", 54# set at 364'
Cmt to surf w/280 sx.

Estimated TOC at 3450'

Perfed & squeezed at 4079'-80' with 100 sks. Class C

Perfs in Shawnee at 4097'-4105'

CIBP at 4628' w/2sx cmt on top
Perfs in Marmaton at 4688'-95'

5-1/2", 15.5# csg set at 5557'.
Cemented with 200 sks. 50/50 Pozmix

RTD=5575'