

WELLBORE DIAGRAM

Bayswater Exploration & Production

Moody 13-29

SWSW Sec 29 5N 65W 6 PM

SHL: 635' FSL, 660' FWL

BHL: 635' FSL, 660' FWL

Weld County CO

05-123-11482

Updated

07/29/14

RWK

G.L.= 4646

K.B.= 4661

15

8-5/8" 24# set at 304' (12-1/4" hole)

Cmt'd to Surf.

TOC: 2900

Calc

<<

>>

Nio Perfs: 6772-6802 (3/29/05)

Nio Frac: 112,000 gal w/ 180,000 20/40

<<

>>

Codell Perf: 7087-7097, 3/8", 21 shots

Codell Frac: 2058 bbl 30 lb x-link w/ 140,000# 20/40 & 15,000# I-prop

Codell Refrac (3/29/05): 115,000 gal w/ 240,000# 20/40

PBTD= 7,120'

4-1/2" 11.5# CSG @ 7190' (7-7/8" O.H.)

TD MD= 7,190'

Cmt'd w/ 850 sx

TD VD= 7,190'