

Pronghorn 14-4

660 FSL660 FWL SWSW 4 5N 61W 6th PM
Lat 40.42472 Long -104.22132 (from footages)
Weld County, Colorado
API #05-123-22430

Spud date 12/5/2004

4648 KB
4638 GL

8.625", 24#/ft Wt, Grade, 362', 12.25" hole
Cemented to surface w/ 150 sxs

Water N/A -- Outcrop
(Within 1 mile radius)

Parkman 3206 '

As found in well:
Pronghorn 14-4

TOC 5480 '

Niobrara 5965 '

Fort Hayes 6243 '

Codell 6280 '

D Sand 6673 '

J Sand 6794 '

Completion Summary

J-Sand completed Jan 2005

J-Sand abandon Jan 2005; CIBP @ 6735' w 2 sxs

Completed Niobrara Jan 2005 (6017' - 6195')

Abandon J-sand CIBP @ 6735'

4 1/2", 10.5#/ft Wt, Grade, 6822', 7 7/8" hole

Cemented with 215 sxs

PBTD 6780 ft
TD 6850 ft

12/13/2004

Updated 7/15/2014 jad