

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400644621

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: GINA RANDOLPH

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4509

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-22259-00

6. County: GARFIELD

7. Well Name: C&C Energy

Well Number: GM 22-13

8. Location: QtrQtr: SWSW Section: 12 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 271 feet Direction: FSL Distance: 1015 feet Direction: FWL

As Drilled Latitude: 39.445610 As Drilled Longitude: -108.064544

GPS Data:

Data of Measurement: 04/03/2014 PDOP Reading: 2.2 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 1304 feet. Direction: FNL Dist.: 2189 feet. Direction: FWL

Sec: 13 Twp: 7S Rng: 96W

** If directional footage at Bottom Hole Dist.: 1327 feet. Direction: FNL Dist.: 2174 feet. Direction: FWL

Sec: 13 Twp: 7S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/11/2014 13. Date TD: 05/16/2014 14. Date Casing Set or D&A: 05/17/2014

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 6535 TVD** 5984 17 Plug Back Total Depth MD 6472 TVD** 5921

18. Elevations GR 5141 KB 5165

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RPM CBL MUDLOGS

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	44	16	0	44	VISU
SURF	13+1/2	9+5/8	32.3	0	1,678	400	0	1,678	VISU
1ST	8+3/4	4+1/2	11.6	0	6,503	990	2,642	6,503	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	1,138		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	3,389		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	5,925		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,405		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: GINA RANDOLPHTitle: PERMIT TECH II

Date: _____

Email: GINA.RANDOLPH@WPXENERGY.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400644916	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400644915	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400644910	PDF-CBL 1ST RUN	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644911	PDF-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644912	LAS-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644913	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644914	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644918	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400644954	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)