



Augustus Energy Resources
Hays 14-35 1S44W

| |
|----------------|
| 13001 |
| Yuma |
| Aaron Carrasco |
| 07/17/14 |

Treatment Report

DESCRIPTION OF JOB EVENTS

Notes:

TD @ (458) FT

RAN (11) JTS, 7", 20#, MEAS (447), SET @ (453), PBSD @ (412)

CMT W/ (275) SX 50/50 POZ, 3% CACL, 0.25% FLO-CEL

15.2 LBS/GAL, 1.07 YLD, 4.20 GAL/SX MIX WATER

DISPLACED= (16.5) BBLS

BBLS TO PIT=(17)

AER

X 7-17-14
Date