

Lincoln County, Colorado

172—Platner loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 3jj8

Elevation: 4,400 to 6,000 feet

Mean annual precipitation: 14 to 16 inches

Mean annual air temperature: 46 to 52 degrees F

Frost-free period: 135 to 155 days

Farmland classification: Prime farmland if irrigated

Map Unit Composition

Platner and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Platner

Setting

Landform: Plains

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Alluvium and/or eolian deposits

Typical profile

A - 0 to 7 inches: loam

Bt - 7 to 15 inches: clay loam

Bk1 - 15 to 40 inches: silty clay loam

Bk2 - 40 to 60 inches: clay loam

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat):

Moderately high (0.20 to 0.60 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Salinity, maximum in profile: Nonsaline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: High (about 10.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3c

Hydrologic Soil Group: C

Ecological site: Loamy plains (R067BY002CO)

Minor Components

Otero

Percent of map unit: 3 percent

Landform: Hills

Landform position (three-dimensional): Side slope

Other vegetative classification: SANDY PLAINS (067XY024CO_1)

Pleasant

Percent of map unit: 3 percent

Landform: Depressions

Ecological site: Plains swale (R067XY010CO)

Ascalon

Percent of map unit: 3 percent

Landform: Plains

Other vegetative classification: SANDY PLAINS (067XY024CO_1)

Fort collins

Percent of map unit: 3 percent

Landform: Plains

Ecological site: Loamy plains (R067BY002CO)

Other vegetative classification: LOAMY PLAINS (067XY002CO_1)

Karval

Percent of map unit: 3 percent

Landform: Hills

Landform position (three-dimensional): Side slope

Other vegetative classification: GRAVEL BREAKS
(067XY063CO_1)

Data Source Information

Soil Survey Area: Lincoln County, Colorado

Survey Area Data: Version 11, Dec 23, 2013