

FORM
17Rev
6/99

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400660954

BRADENHEAD TEST REPORT

Step 1. Record all tubing and casing pressures as found. Step 2. Sample now. If intermediate or surface casing pressure > 25 psi. In sensitive areas, 1 psi.
Step 3. Conduct Bradenhead test. Step 4. Conduct intermediate casing test. Step 5. Send report to BLM within 3 days and to OGCC within 10 days. Include wellbore diagram if not previously submitted or if wellbore configuration has changed since prior program. Attach gas and liquid analyses if sampled.

1. OGCC Operator Number: 47120 3. BLM Lease No: _____
2. Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP
4. API Number; 05-123-20554-00 5. Multiple completion? ☐ Yes ☐ No
6. Well Name: STREAR Number: 5-10
7. Location (QtrQtr, Sec, Twp, Rng, Meridian): SWNW,10,2N,67W,6
8. County WELD 9. Field Name: WATTENBERG
10. Minerals: ☐ Fee ☐ State ☐ Federal ☐ Indian

11. Date of Test: 07/18/2014

12. Well Status: ☐ Flowing
☐ Shut In ☐ Gas Lift
☐ Pumping ☐ Injection
☐ Clock/Intermitter
☒ Plunger Lift

13. Number of Casing Strings:
☐ Two ☐ Three ☐ Liner?

14. EXISTING PRESSURES

Record all pressures as found	Tubing: 844 Fm: _____	Tubing: _____ Fm: _____	Prod Csg 844 Fm: _____	Intermediate Csg: _____	Surf. Csg 133
-------------------------------	--------------------------	----------------------------	---------------------------	----------------------------	------------------

BRADENHEAD TEST

Buried valve? ☐ Yes ☒ NoConfirmed open? ☒ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open surface casing (bradenhead) valve (if no intermediate casing, monitor only the production casing and tubing pressures.) Record pressures at five minute intervals Define characteristics of flow in "Bradenhead Flow" column using letter designations below:

O = No Flow; C = Continuous; D = Down to 0; V = Vapor
H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

BRADENHEAD SAMPLE TAKEN?

☐ Yes ☒ No ☐ Gas ☐ LiquidCharacter of Bradenhead fluid: ☐ Clear ☐ Fresh☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number:

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
00:00	<input type="checkbox"/> 844	<input type="checkbox"/>	<input type="checkbox"/> 844		G
05:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		G
10:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		G
15:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		C
20:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		C
25:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		C
30:00	<input type="checkbox"/> 845	<input type="checkbox"/>	<input type="checkbox"/> 845		C

Instantaneous Bradenhead PSIG at end of test: > 1

INTERMEDIATE CASING TEST

Buried valve? ☐ Yes ☐ NoConfirmed open? ☐ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open the intermediate casing valve. Record pressures at five minute intervals Characterize flow in "Intermediate Flow" column using letter designations below:

O = No Flow; C = Continuous; D = Down to 0; V = Vapor
H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

INTERMEDIATE SAMPLE TAKEN?

☐ Yes ☐ No ☐ Gas ☐ LiquidCharacter of Intermediate fluid: ☐ Clear ☐ Fresh☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number:

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		

Instantaneous Intermediate Casing PSIG at end of test: >

Comments:

WELL SHUT IN UPON ARRIVAL. SURFACE CASING PRODUCED 45 GALLONS OF CONDENSATE. MONITORED EXTRA THIRTY MINUTES. SHUT IN FOR 15 MINUTES PRESSURE BUILT BACK UP TO 127 PSI OF GAS. PREFORMED FORM 17 TEST AS REQUESTED BY ANNE KREMER.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Test Performed By: KYLE KASTEN Title: NON-EMPLOYEE JOB Phone: (970) 590-1196

Signed: LISA WEICHEL Title: _____ Date: 8/11/2014

Witnessed By: LISA WEICHEL Title: NON-EMPLOYEE JOB Agency: ANADARKO