



---

## Re: PA 34-6 (API# 05-045- 22410) Low TOC notification

1 message

---

**Krabacher - DNR, Jay** <jay.krabacher@state.co.us>

Tue, Aug 12, 2014 at 3:41 PM

To: "Schant, Jennifer" <Jennifer.Schant@wpxenergy.com>

Cc: "Haddock, Reed" <Reed.Haddock@wpxenergy.com>, "Neifert-Kraiser, Angela" <Angela.Neifert-Kraiser@wpxenergy.com>, "Randolph, Gina" <Gina.Randolph@wpxenergy.com>, "Salazar, Sandi" <Sandra.Salazar@wpxenergy.com>, "Weybright, Michele" <Michele.Weybright@wpxenergy.com>, "Andrews, David" <David.Andrews@state.co.us>

Jennifer:

WPX has COGCC concurrence to continue with completions as planned. Of course, be sure to have the bradenhead pressure monitored, and if it increases 200 psi over the starting pressure COGCC must be notified (Rule 341).

Regards,

Jay Krabacher

On Tue, Aug 12, 2014 at 3:09 PM, Schrant, Jennifer <Jennifer.Schant@wpxenergy.com> wrote:

Hi Jay,

This email is to notify you that the PA 34-6 on the PA 24-6 pad has a low top of cement. Details of this well include:

PA 34-6 (05-045-22410)- MV Well

- This well is a new drill
- Top of Cement- 3872'
- This well **does not** cover 200' above the top of the Mesa Verde (Geology pick: 3499')
- This well **does** cover the top of gas (Geology pick: 4606')
- Bradenhead pressure is 0 psi
- The planned top perf depth is 4619'

The well is scheduled to frac on 8/19/2014. Please advise.

Thank you,

*Jennifer Schrant*

EDP Engineer I-

Piceance Completions

Office Phone: (303) 629- 8402

Cell Phone: (303) 885-7752

Email: [jennifer.schrant@wpxenergy.com](mailto:jennifer.schrant@wpxenergy.com)



--  
Jay Krabacher

N W Area Engineer



**COLORADO**

**Oil & Gas Conservation  
Commission**

Department of Natural Resources

P 970.625.2497 x4

C 970.589.6180

796 Megan Ave., Suite 201, Rifle, CO 81650

[jay.krabacher@state.co.us](mailto:jay.krabacher@state.co.us) | [www.colorado.gov/cogcc](http://www.colorado.gov/cogcc)